

SURVEY & REMONUMENTATION

MAR 19 1998

1997 Newaygo County Remonumentation Project

NEWAYGO COUNTY
REGISTER OF DEEDS
LINDA M. BROWN

**LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT of Act 74, Mich. P.A. 1970**

'98 MAR 6 PM 12 34

SECTION

For corners in
Newaygo
(County)

Located in:

Corner Code #

Linda M. Brown

- | | | |
|---------------------------------------|-----------------------------|-------|
| 1. Public Land Survey | T <u>11</u> N R <u>13</u> W | F-5 |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

VOL. 2

65

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Norman L. Ochs, in a field survey on September 15, 1997, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

South One Quarter Corner, Section 9, Ashland Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. James H. Mullett 1836
12" Hemlock S55°W 17 Links (11.22') #1
12" Hemlock N65°E 8 Links (5.28') #2

Newaygo Engineering and Survey Company
August 17, 1983 Drawing Number 83144B&M
Found 1" Square Bolt in monument box

Newaygo County Road Commission Sheet
1" Iron
Project Marker S65°W 49.3' #3
Northeast Corner School Foundation S29°W 104.26' #4
Service Pole S29°E 82.2' #5
"X" East Curb S66°E 51.6' #6
"X" West Curb S65°W 51.7' #6
18" White Pine East 93.6' #8

William Fries, Jr. R.L.S. #30389
June 1990 Found 1 1/8" Square Bolt
18" White Pine N19°E 75.07' #9

OVER ↵

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 1 1/4" Square Bolt 16" long in monument box in centerline of East and West blacktop road and in centerline of blacktop road going South. The centerline of gravel road going North is 4 feet West. The condition of the recorded witnesses are: #1 thru #3 gone, #4 good condition, #5 gone, #6 thru #8 good condition, #9 gone, #10 and #11 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed 1 1/4" Square Bolt and set a 2 3/4" diameter Harrison cast iron monument 18" long marked "County Surveyor" in monument box as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

Northeast Corner School Foundation S33°W 103.96' #4
"X" East Curb S66°E 51.6' on top. #6
"X" West Curb S80°W 51.75' on top. #7
32" White Pine N81°E 93.61' Found tag #30389 in South side of tree. #8
Power Pole S51°W 45.87' Found tag #30389 in Northwest side of pole. #10
Telephone pedestal Westerly Bolt top N30°W 55.73' #11
Project Marker S60°W 60.98'

Signed by Norman L. Ochs Date October 10, 1997

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971
Revised May 14, 1975
Revised Jan., 1983

Approved by Peer Review Group on October 14, 1997
Norman L. Ochs, County Representative.



N. L. O.

A. Description (cont.)

William Fries, Jr. R.L.S. #30389

1993 Found 1 1/8" Square Head Bolt

18" White Pine N19°E 75.07' #9

29" White Pine N73°E 93.92' #8

Power Pole S46°W 45.87' #10

"X" West end top of Curb S35°E 51.74' #7

Telephone Pedestal Westerly Bolt Top N41°W 55.74' #11