

MAY 28 1997

COMMISSION

1996 Newaygo County Remonumentation Project

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

'97 FEB 12 PM 4 45

Linda M. Brown

For corners in Newaygo (County) Located in: Corner Code #

1. Public Land Survey T 11 R 13W G-3
 T R
 T R
 T R

2. Property Controlling in Section S T R
 S T R

3. Miscellaneous Property in Sec. S T R
 S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

VOL. 1 PAGE 224

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	0		5		4		3		2				
3							●						
4	7		0		0		10		11		12		
5													
6	16		17		18		19		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Norman L. Ochs, in a field survey on November 1, 1996, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Southeast Corner, Section 4, Ashland Township, Newaygo County, Michigan

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. James H. Mullett 1838
 10" Aspen N25°W 24 Links (15.84')#1
 18" Pine N64°E 15 Links (9.90')#2
 Measured 79.90 Chains (5273.40') from the Southwest Corner of Section 4 to the Southeast Corner of Section 4 and measured 80.04 Chains (5282.64') from the Southwest Corner of Section 3 to the Southeast Corner of Section 3 and measured 39.95 Chains (2636.70') from the South One Quarter Corner of Section 4 to the Southeast Corner of Section 4 and measured 40.02 Chains (2641.32') from the Southwest Corner of Section 3 to the South One Quarter Corner of Section 3.

Winfield S. Merrill (County Surveyor)
 Book A Page 71 June 10, 1882
 Measured 39.46 Chains (2604.36') from the South One Quarter Corner of Section 4 to the Southeast Corner of Section 4 and measured 40.45 Chains (2669.70') from the Southwest Corner of Section 3 to the South One Quarter Corner of Section 3.

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Dug and found nothing. Corner is in a two foot cut area. Set corner in fence line on ground going South and in the centerline of East and West road. I measured 2614.58 feet from the South One Quarter Corner to the Southeast Corner of Section 4 and measured 2668.32 feet from the Southeast Corner of Section 4 to the South One Quarter Corner of Section 3 and measured 5282.90 feet from the South One Quarter Corner of Section 3 to the South One Quarter Corner of Section 4 and measured 2627.29 feet from the Southeast Corner to the East One Quarter Corner of Section 4 and the condition of the recorded witnesses are: #1 and #2 gone.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Set a 4" diameter Harrison cast iron monument 20" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

- 12" Elm S30°W 37.35' Set spike in Southeast side of tree.
- 8" Ash N78°E 83.70' Set spike in Southerly side of tree.
- 6" Red Pine N20°E 64.07' Set spike in West side of tree.
- 14" Jack Pine N30°W 44.03' Set spike in Southwest side of tree.

Signed by Norman L. Ochs Date November 30, 1996
 Norman L. Ochs

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971
 Revised May 14, 1975
 Revised Jan., 1983

Approved by Peer Review Group On December 11, 1996
 Norman L. Ochs, County Representative.

N. L. O.

