

YEAR 02 1999

1998 Newaygo County Remonumentation Project

99 FEB 17 PM 3 33

SECTION

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

Linda M. Brown

For corners in Newaygo (County) Located in: Corner Code # 1. Public Land Survey T 11N R 13W G-10 2. Property Controlling in Section S T R 3. Miscellaneous Property in Sec. S T R 4. Lot No. Recorded Plat 5. Private Claims

VOL. 2 162

Register of Deeds Stamp & File Number

I, Norman L. Ochs, in a field survey on November 2, 1998, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. Cell (10, G) contains a black dot.

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

East One Quarter Corner, Section 28, Ashland Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. James H. Mullett 1838 6" Beech N68°E 8 Links (5.28')#1 12" Beech S29°W 25 Links (16.5')#2

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found nothing. Established corner equal distance and on line between the Southeast Corner and the Northeast Corner. The remnants of This position fits existing occupation. The condition of the recorded witnesses are: #1 and #2 gone.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Set a 4" diameter Harrison cast iron monument 36" long marked "County Surveyor" with stone pile around as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

- 20" Beech (blazed) S25°E 12.72' Set spike with tag #22439 in Northerly side of tree. 18" Maple (blazed) N62°E 8.00' Set spike with tag #22439 in Westerly side of tree. 10" Cherry (blazed) S28°W 33.64' Set spike with tag #22439 in East side of tree. 10" Maple (blazed) N77°W 45.90' Set spike with tag #22439 in South side of tree.

Signed by Norman L. Ochs Date December 18, 1998

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971 Revised May 14, 1975 Revised Jan., 1983

Approved by Peer Review Group On December 22, 1998 Norman L. Ochs, County Representative.

N.L.O.

