

SURVEY & REMONUMENTATION

MAR 19 1998

1997 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

'98 MAR 6 PM 12 34

SECTION

For corners in Newaygo (County) Located in: _____ Corner Code # _____

1. Public Land Survey T 11N R 14W E-7
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Linda M. Brown

VOL. 2

61

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on June 26, 1997, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Southwest Corner, Section 16, Bridgeton Township, Newaygo County, Michigan

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Mullett & Brookfield 1837
 10" Tamarack N77°W 18 Links (11.88') #1
 20" Tamarack S73°E 16 Links (10.56') #2
 Measured 80.10 Chains (5286.60') from the Southeast Corner to the Southwest Corner of Section 17.

William M. Jacques (County Surveyor)
 Book 24 Page 1 March 11, 1908
 Measured 39.77½ Chains (2625.15') from the Southeast Corner to the South One Quarter Corner of Section 17.

Newaygo Engineering and Survey Company
 Measured 2690.23 feet from the Northeast Corner to the East One Quarter Corner of Section 20 and measured 2658.71 feet from the Southwest Corner to the South One Quarter Corner of Section 16.

Charles F. Lewandoski R.L.S. #7867
 August 1977 Survey #6663
 Steel Fence Post (Set)
 8" Maple N05°W 3.1' #3
 12" Cedar S10°W 42.3' #4
 14" White Pine S80°E 41.8' #5
 To edge of swamp East 132± (Government Distance) #6
 Measured 2668.92 feet from the Southwest Corner to the South One Quarter Corner of Section 16.

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found Steel "T" Fence post 4½ feet long and the condition of the recorded witness are: #1 and #2 gone, #3 dead and fallen, #4 and #5 good condition, #6 gone.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed steel "T" fence post and set a 4" diameter Harrison cast iron monument 36" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

- 14" Maple N20°W 3.25' Set nail with tag in East side of tree. #4
- 14" Cedar S13°W 42.16' Set nail with tag in Westerly side of tree. #5
- 10" Ash West 15.63' Set nail with tag in South side of tree.
- 8" Cedar N30°E 11.36' Set nail with tag in Westerly side of tree.

Signed by Norman L. Ochs Date September 8, 1997
 Norman L. Ochs

Surveyor's Michigan License No. 22439 Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Approved by Peer Review Group on September 9, 1997 Revised May 14, 1975

Norman L. Ochs, County Representative. Revised Jan., 1983

N.L.O.

