

**SURVEY &
REMONUMENTATION**

APR 24 1994 NEWAYGO COUNTY REMONUMENTATION PROJECT

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

VOL **001** PAGE **84**

For corners in

<u>Newaygo</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>11N</u> R <u>14W</u>	<u>F-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

NEWAYGO COUNTY
REGISTER OF DEEDS
MARLENE TOOGOOD

'95 MAR 14 PM 3 53

Marlene Toogood

Register of Deeds Stamp & File Number

I, Norman L. Ochs, in a field survey on April 21, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

S-1/4 cor., Sec. 16, Bridgeton Twp., Newaygo County MI

A. Description of original monument and accessories and/or subsequent restoration:

GLO John Mullett 1837
Lynn 18" N44°E 14 lks (9.24') #1
24" Hemlock N30°E 38 lks (25.08) #2

NCR Sheet Sleigh Shoe
T.Pole N45°W 53.5' #5
15" Tw. Hickory N10°E 52.7' #3
Conc. Post East 31.2' #4

1950 Ralph A. Smith #3421
Sleigh Shoe & stone
Tw. Hickory N12°E 52.4' #3 16"
Field Book 56, Pg. 46
Conc. Post East 31.2' #4

1960 Ralph A. Smith #3421 Sleigh Shoe
Field Book 56, Pg. 65
Post East 31.2' #3
T.Pole N45°W 53.5' #5
15" Hickory N10°E 52.7' #3

-OVEI

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On April 21, 1994, I, Norman L. Ochs, found sleigh shoe and stone. Replaced (in the exact location) with a 4" Harrison cast iron monument.

Condition of recorded witnesses is: #1 gone, #2 gone, #3 good condition, #4 good condition, #5 gone, #6 good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted 4" Harrison cast iron monument 20" long as a substantial marker for the Section Corner and is accepted as a careful and faithful reestablishment of the original corner.

12" Cherry N59°W 52.63' Spike in Nly side of tree. #6
Tw. Hickory N11°E 52.70' Spike in East side of tree #3
10"-12" Clm. Elm N70°W 73.64' Spike in Nly side of tree
NW cor. conc. Post East 31.20" #4



Signed by Norman L. Ochs

Date November 3, 1994

Surveyor's Michigan License No. 22439

Approved by Peer Review Group on November 10, 1994.
Norman L. Ochs, County Representative.

A cont.

Charles F. Lewandowski RLS #7867
August 1977 Survey #6663
Sleigh Shoe
20" Tw. Hickory N13°10'E 52.7' #3
8" Cherry N58°40'W 52.7' #6
Center of conc. post East 31.7' #4