

**SURVEY & REMONUMENTATION**

MAR 02 1999

1998 Newaygo County Remonumentation

LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT of Act 74, Mich. P.A. 1970

NEWAYGO COUNTY  
REGISTER OF DEEDS  
LINDA M. BROWN

'99 FEB 17 PM 3:33

*Linda M. Brown*

**SECTION**

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>11N</u> R <u>14W</u>	<u>K-2</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

VOL. 2

157

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Norman L. Ochs, in a field survey on January 7, 1998, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

East One Quarter Corner, Section 2, Bridgeton Township, Newaygo County, Michigan.

**A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:**

G.L.O. John Mullett 1837  
18" Hemlock N38°E 22 Links (14.52')#1  
12" Beech N75°W 33 Links (21.78')#2

Newaygo County Road Commission Sheet  
15" Elm S85°E 26.9' #5  
12" Elm S40°E 26.0' #6

Phillip A. Harrison (County Surveyor)  
1881 Book A Pages 29 and 30  
20" Black Ash Stump S35°E 47 Links (31.02')#3  
20" Hemlock N27°E 63 Links (41.58')#4

Norman L. Ochs R.L.S. #22439  
Drawing Number 77025AC April 20, 1977  
Iron in monument box  
10" Hemlock S69°E 58.86' #7  
8" Elm S46°W 73.38' #8  
Telephone Pole N39°W 56.18' #9

OVER ↙

**B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:**

Found 1/2" Pipe 2 feet long in centerline of bituminous road going North and South and the centerline of gravel road going West is 2 feet South and the condition of the recorded witnesses are: #1 thru #12 gone.

**C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:**

Removed 1/2" Pipe and set a 2 3/4" Harrison cast iron monument 20" long marked "County Survey" in monument box as a substantial marker for the quarter corner and is accepted as a careful and faithful reestablishment of the original corner.

36" White Oak S85°W 121.02' Set spike and tag in North side of tree.  
12" White Pine N60°W 91.96' Set spike and tag in South side of tree.  
14" Red Pine S73°W 94.60' Set spike and tag in Southeast side of tree.  
8"-6" Twin Ash S20°E 67.14' Set spike and tag in Northeast side of tree.

Signed by *Norman L. Ochs* Date November 5, 1998

Surveyor's Michigan License No. 22439 Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Approved by Peer Review Group on December 22, 1998  
Norman L. Ochs, County Representative.

Revised May 14, 1975  
Revised Jan., 1983

*M.L.O.*



A. Description (cont.)

Newaygo County Road Commission Sheet

Telephone Pole S45°W 42.5' #10

Telephone Pole N39°W 56.18' #9

8" Elm S46°W 75.38' #8

10" Hemlock S69°E 58.86' #7

Norman L. Ochs R.L.S. #22439

1978 Found ¾" Pipe in monument box

Telephone Pole S30°W 67.47' #10

Telephone Pole N25°W 79.38' #11

24" White Oak S80°W 120.1' #12

SURVEY &  
REMONUMENTATION

MAR 02 1999

SECTION