

MAR 02 1999

1998 Newaygo County Remonumentation

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

'99 FEB 17 PM 3 33

SECTION

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

Linda M. Brown

For corners in Newaygo Located in: _____ Corner Code # _____
 (County)

1. Public Land Survey T 11N R 14W _____ K-3
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

VOL. 2 158

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on January 7, 1998, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Southeast Corner, Section 2, Bridgeton Township, Newaygo County, Michigan

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. John Mullett 1837
 12" Beech N70°E 24 Links (15.84') #1
 12" Beech N15°W 10 Links (6.60') #2

Patrick A. Salisbury R.L.S. #13594
 1974 1/2" Iron Rod in monument box
 Telephone Pole S50°W 50.45' #5
 30" White Oak S45°±E 103.30' #6
 Power Pole N35°±E 90.35' #7

Winfield S. Merrill (County Surveyor)
 Book A Pages 107 and 108 November 7, 1888
 40" Pine N04°W 128 1/2 Links (84.81') #3
 38" Pine S63°W 106 Links (69.96') #4

Newaygo County Road Commission Sheet
 Telephone Pole S50°W 50.1' #5
 15" White Pine N35°W 38.2' #8
 15" Maple S40°W 46.5' #9
 Guy Pole S40°E 47.2' #10

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 1/2" Rerod in 1 1/2" X 34" Well Point and a Pine root stake. The centerline of the North and South bituminous road is 3 feet East and in the centerline of the East and West gravel road and the condition of the recorded witnesses are: #1 thru #5 gone, #6 and #7 good condition, #8 thru #10 gone.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed 1/2" Rerod, 1 1/2" X 34" Well Point, Pine root stake and set a 2 3/4" diameter Harrison cast iron monument 20" long marked "County Survey" in monument box as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

36" White Oak S64°E 103.33' Found spike in Northerly side of tree. #6
 Power Pole N38°E 91.75' Found P.K. in Southeast side of pole. #7
 8" Spruce S46°E 73.10' Set spike and tag in Southwest side of tree.
 6" White Pine N15°W 166.99' Set spike and tag in Northeast side of tree.

Signed by Norman L. Ochs Date November 5, 1998
 Norman L. Ochs

Surveyor's Michigan License No. 22439 Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Approved by Peer Review Group on December 22, 1998
 Norman L. Ochs, County Representative.

Revised May 14, 1975
 Revised Jan., 1983



M. L. O.