

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 12 N. 6., R. 12 W.	I-8; I-9; J-9
2. PROPERTY CONTROLLING IN SECTION	T. N. S., R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S., R. E. W.	
4. LOT NO.	RECORDED PLAT	
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on February 6, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- I-8 Re-established 1/4 Cor. to Sec's 22 & 23 on line between NW & SW Cor's. of Sec.23 and on line across E 1/4 Cor. & Fd. 1/2 pipe near Ctr. Sec. 23. Computed position for 1/4 Cor. per Zimmerman Sur. of Sec.22 would be 2'-South S.P. position would be 4'-North.
 - I-9 Re-estab. SW Cor. of Sec. 23 record per Norm Ochs Cert. Survey, Dwg. No. 77090-B, per our tie to his westerly boundary. This fits C.F. Zimmerman Survey of N 1/2 Sec. 27 in 1958.
 - J-9 Fd. re-rod that fits Co. Rd. Comm. Wits.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-8	I-9	J-9
Set DNR Mon. & Ced. Post	Set DNR Mon. & Ced. Post	Fd. 3/4 re-rod
19" B.Oak N65°W 9.51	7" W. Ash N35°W 26.1	*12" W.Oak N58°W 61.0
13" B.Oak N65°E 33.56	12" R.Oak N60°E 15.5	*13" W.Pine N37°E 47.3
11" W.Pine S20°W 80.46	13" W.Oak S60°E 26.4	*19" W.Oak S53°E 49.4
Fd. 1/2" pipe	8" R.Maple S45°W 3.4	Set Ced. Post w/Loc. Tag
S32°10'W 54.22		Due W 33'
Fd. 1/2" pipe		Ctr. N-S gravel rd
S68°23'E 101.38		Due W 5'+
		*equals Co. Rd. Comm. Wits.


SIGNED BY Carl F. Roser 2-12-79 DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE

APPROVED AND SIGNED BY _____ DATE



BROOKS TOWNSHIP
NEWAYGO COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. _____