

MAY 28 1997

COMMISSION

1996 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

'97 FEB 12 PM 4 45

For corners in Newaygo (County) Located in: Corner Code # 1. Public Land Survey T 12N R 12W B-13 2. Property Controlling in Section S T R 3. Miscellaneous Property in Sec. S T R 4. Lot No. Recorded Plat 5. Private Claims

Linda M. Brown

VOL. 1 PAGE 226

Register of Deeds Stamp & File Number

Table with 13 columns (A-M) and 13 rows (2-13) for recording deed information.

I, Norman L. Ochs, in a field survey on October 9, 1996, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

South One Quarter Corner, Section 31, Brooks Township, Newaygo County, Michigan

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

- G.L.O. John Hodgson 1837 10" Beech N41°E 36 Links (23.76') #1 18" Pine N75°W 12 Links (7.92') #2 Patrick A. Salisbury R.L.S. #13594 3/4" Pipe April 18, 1975 16"-8" Twin Cherry S20°E 30.80' #3 14" White Oak S55°E 47.31' #4 8" Red Oak N30°E 56.41' #5

- Charles E. Fricke R.L.S. #21781 December 17, 1991 LCRC #1107 Found 1/2" Iron Pipe 10" Oak N50°W 57.00' #6 Property Iron North 33.00' #7 18" Oak N63°E 96.7' #8 North One Quarter Corner, Section 6, Grant Township West 14.52' #9

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 1/2" Pipe in centerline of East and West blacktop road and on centerline of old fence on ground going North and old fence on ground going South is 15 feet East and the condition of the recorded witnesses are: #1 thru #4 gone, #5 thru #9 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed 1/2" Pipe and set a 4" diameter Harrison cast iron monument 20" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

- 14" Red Oak N34°E 56.54' Set spike and tag in Southeast side of tree. #5 14" Oak N45°W 57.11' Set spike and tag in Southwest side of tree. #6 1/2" Pipe N05°E 33.01' #7 20" White Oak N70°E 96.74' Set spike and tag in South side of tree. #8 1/2" Rod, North One Quarter Corner, Section 6, T11N R12W West 14.52' #9

Signed by Norman L. Ochs Date October 17, 1996

Surveyor's Michigan License No. 22439 Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Approved by Peer Review Group On December 11, 1996 Norman L. Ochs, County Representative.

Revised May 14, 1975 Revised Jan., 1983

N. L. O.

