

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

VOL 001 PAGE 88

For corners in

<u>Newaygo</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>12N</u> R <u>12W</u>	<u>I-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

NEWAYGO COUNTY,  
REGISTER OF DEEDS  
MARLENE TOOGOOD

'95 MAR 14 PM 3 53

Register *Miscellaneous Stamp & Fee Number*

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3									●				
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs in a field survey on September 3, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**  
NW Corner, Sec. 11, Brooks Twp., Newaygo County MI

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. John Hodgson 1837 #1 NCRC Sheet  
10" B. Oak S20°E 101 lks (66.66') W. Oak NW 46.5' #3  
12" W. Oak N70°E 130 lks (85.80') #2 USGS Mon. SW 41.5' #4

Ralph A. Smith RLS #3421

W. Oak NW 46.5' #3  
USGS Mon SW 41.5' #4

Dec. 16, 1963 Robert A. Griffin RLS #13584  
LCRC #86

Found red brick. Set on end w/broken glass & crockery around.

Set 5" Sq. reinforced conc. mon.  
10" W. Pine N57°E 74.85' #5

-OVER-

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5" square conc. mon set by R. A. Griffin RLS #13584.  
Condition of witnesses are No. 1, 2, 3, and 7 are gone.  
No. 8 is now a stump, No. 4, 5, 6 are good.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 5" square conc. mon 2' deep, and is accepted as a careful and faithful reestablishment of the position of the original corner.

10" W. Pine S51°E 78.83' Spk. on SW side. #6  
15" W. Pine N57°E 74.84' Spk. on SE side. #5  
Center of USGS mon. S51°W 41.48' Cen #4  
8" Red Oak 40.99' Spk. on N. side.



Signed by Norman L. Ochs  
Norman L. Ochs

Date October 19, 1994

Surveyor's Michigan License No. 22439

Approved by Peer Review Group on November 10, 1994.  
Norman L. Ochs, County Representative.

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

SURVEY &  
REMONUMENTATION

DEC 07 2000

SECTION

A. cont.

8" W. Pine S51°E 78.80' #6  
USGS Mon. elev. 800.0' S51°W 41.48' #4  
6" x 7' Cedar Post S51°W 42.90' #7  
13"-16" Tw. W. Oak N30°W 47.35' #8  
(Stump now)

Patrick A. Salisbury RLS #13594  
June 1969  
Found 5' Sq. reinforced conc. mon.  
10" W. Pine N57°E 74.85' #5  
8" W. Pine S51°E 78.8' #6  
USGS Mon. S51°W 41.48' #4  
Measured 5295.23 ft. from the NW cor  
to the NE cor. of Sec. 11.

May 26, 1977 Newaygo Eng. & Survey Co.  
Fnd. 5" Sq. conc. mon.  
10" W. Pine N57°E 74.85' #5  
8" W. Pine S51°E 78.80' #6  
USGS Mon. elev. 800.0' S51°W 41.48' #4  
6" x 7' Cedar Post S51°W 42.90' #7  
Measured 2677.54 ft. from the NW cor.  
to the W-1/4 cor. of Sec. 11.  
Measured 2586.38 ft. from the SW cor.  
to the W-1/4 cor. of Sec. 2. Meas-  
ured 2647.34 ft. from the NW cor to  
the N-1/4 cor. of Sec. 11.

See recorded survey in Series  
I, No. 482.

SURVEY &  
REMONUMENTATION

DEC 07 2000

SECTION