

**SURVEY & REMONUMENTATION**

**MAR 19 1998**

**1997 Newaygo County Remonumentation Project**

NEWAYGO COUNTY  
REGISTER OF DEEDS  
LINDA M. BROWN

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT of Act 74, Mich. P.A. 1970**

'98 MAR 6 PM 12:34

*Linda M. Brown*

For corners in  
Newaygo  
(County)

Located in:

Corner Code #

- 1. Public Land Survey T 11N R 12W  
T 12N R 12W  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

L-1  
L-13

**VOL. 2**

**69**

**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on July 8, 19 97, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**Note: This Corner is common to both sections.**

North One Quarter Corner, Section 1, Grant Township, Newaygo County, Michigan  
South One Quarter Corner, Section 36, Brooks Township, Newaygo County, Michigan

**A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:**

G.L.O. Brookfield and Hodgson 1838  
7" Maple N25°W 7 Links (4.62') #1  
8" Maple N43°E 13 Links (8.58') #2

William M. Jacques (County Surveyor)  
Book 14 Page 24 April 21, 1904  
24" Pine Stump S27°W 51' #3

Newaygo Engineering and Survey Company  
1984 ¾" Pipe  
14" Black Oak S20°W 24.8' #4  
12" Twin Oak S65°E 57.0' #5  
10" Black Oak N15°W 68.22' #6

Ralph A. Smith R.L.S. #3421  
Book 70 Page 1 thru 3 June 30, 1959  
Set ¾" Pipe half-way between corners  
8" Black Oak S20°W 24.8' #4  
8" Twin Oak S65°E 57.0' #5  
10" Black Oak N15°W 67.7' #6

Robert Wetherell R.L.S. #24624  
April 3, 1978 File Number 3010-78  
14" Black Oak S20°W 24.8' (old bearing tree) #4  
12" Oak S65°E 57.0' (old bearing tree) #5  
14" Black Oak N15°W 67.7' (old bearing tree) #6

OVER ↘

**B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:**

Found ¾" X 20" Iron pipe in centerline of East and West gravel road and on West edge of pine plantation going North and the condition of the recorded witnesses are: #1 and #2 gone, #3 remains of stump, #4 thru #7 good condition.

**C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:**

Removed ¾" X 20" Iron pipe and set a 4" diameter Harrison cast iron monument 20" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

- 28" Black Oak S21°W 24.8' Found spike in East side of tree. #4
- 24"-24" Twin Black Oak S56°E 57.0' Set spike with tag in Southwest side of tree. #5
- 22" Black Oak N06°W 68.25' Found spike in East side of tree. #6
- 16"-14" Black Oak N01°E 106.94' Found nail in root in Southeast side of tree. #7

Signed by Norman L. Ochs Date September 8, 1997  
Norman L. Ochs

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors Jan. 14, 1975  
Revised May 14, 1975  
Revised Jan., 1983

Approved by Peer Review Group on September 9, 1997  
Norman L. Ochs, County Representative.

*N.L.O.*



A. Description (cont.)

William Fries, Jr. R.L.S. #30389

LCRC #1026 Survey recorded in Liber 351, Page 4573

Found 1" Pipe

15"-16" Twin Oak S62°E 56.94' #5

18" Oak S16°W 24.36' #4

17" Oak N13°W 68.18' #6

12"-12" Twin Oak N05°W 106.86' #7