

MAR 02 1999

**1998 Newaygo County Remonumentation Project**

NEWAYGO COUNTY  
REGISTER OF DEEDS  
LINDA M. BROWN

**LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT of Act 74, Mich. P.A. 1970**

FEB 17 PM 3 37

**SECTION**

For corners in Newaygo (County) Located in: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey T 12N R 13W \_\_\_\_\_ E-7 \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

*Linda M. Brown*

**VOL. 2 194**

**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on June 15, 1998, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Southwest Corner, Section 16, Garfield Township, Newaygo County, Michigan.

**A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:**

G.L.O. J.H. Mullett 1837 10" Beech N70°W 38 Links (25.08')#1 6" Beech S15°E 40 Links (26.4')#2	Winfield S. Merrill (County Surveyor) Book A Pages 87 and 88 April 13, 1887 Book A Pages 113 and 114 March 27 to April 3, 1889 36" Pine S59½°E 80 Links (52.8')#3 6" Red Oak N60°E 67 Links (44.22')#4
Newaygo County Road Commission Sheet Monument Box	Ralph A. Smith R.L.S. #3421 Book 56 Pages 50 and 55 June 9, 1952 Monument box
Patrick A. Salisbury R.L.S. #13594 Consumers Power Company Section Break, Section 20, T12N R13W. 1968 Found monument box.	

**OVER**

**B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:**

Found 12" bolt with ¾" X ¾" head in monument box on line ± with the centerline of the North and South bituminous road and the centerline of the East and West bituminous road is 2.5 feet ± South. The condition of the recorded witnesses are: #1 thru #4 gone, #5 and #6 good condition, #7 and #8 gone.

**C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:**

Removed Bolt and monument box and set a 2¾" X 20" Harrison cast iron monument marked "County Survey" in new 8" diameter monument box as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

Power Pole S40°W 65.25' Found P.K. nail with tag (illegible) in Southeasterly side of pole. #5  
 Power Pole N40°W 61.61' Found P.K. nail with tag (illegible) in Northeasterly side of pole. #6  
 12" Red Oak (blazed) N43°E 61.32' Found spike in Northwest side of tree.  
 34" Maple S70°E 108.33' Set spike with tag #22439 in North side of tree.

Signed by Norman L. Ochs Date October 20, 1998  
 Norman L. Ochs

Surveyor's Michigan License No. 22439 Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Approved by Peer Review Group on October 22, 1998  
 Norman L. Ochs, County Representative.

*N.L.O.*



Revised May 14, 1975  
 Revised Jan., 1963

A. Description (cont.)

Maurice J. Rosema R.L.S. #27459

March 1987 Found 1" square bar in monument box.

Power Pole Southwest 65.32' #5

Power Pole Northwest 61.64' #6

50" Oak Northeast 78.56' #7

Concrete curb Southeast 45.39' #8

SURVEY &  
REMONUMENTATION

MAR 02 1939

SECTION