

MAR 19 1998

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

SECTION

1997 Newaygo County Remonumentation Project

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

'98 MAR 6 PM 12 35

Linda M. Brown

Form with fields: For corners in Newaygo (County), Located in: T 12N R 13W, Corner Code # H-3, 1. Public Land Survey, 2. Property Controlling in Section, 3. Miscellaneous Property in Sec., 4. Lot No., 5. Private Claims

VOL. 2

78

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13. Cell (3, H) contains a black dot.

I, Norman L. Ochs, in a field survey on February 24, 19 97, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

South One Quarter Corner, Section 3, Garfield Township, Newaygo County, Michigan

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. J.H. Mullett 1839 8" Beech S49°E 17 Links (11.22')#1 4" Maple N05°E 24 Links (15.84')#2

Lyle S. Shepherd R.L.S. #503 Witness Book Number 2, Page 85 14" Oak S05°E 30' #5 10" Maple S50°E 53' #6

Winfield S. Merrill (County Surveyor) Book A Pages 65 and 66 May 13, 1882 36" Pine S36½°W 38 Links (25.08')#3 30" Red Oak N81°E 71 Links (46.86')#4

C.F. Zimmerman P.E. #7301 September 16, 1967 30" White Oak South 30.4' #5 14" Maple S50°E 53.3' #6

Newaygo Engineering and Survey Company June 17, 1987 Drawing Number 87106M&B Found 1" Axle 26" White Oak S05°E 30.77' #5 18" Maple S50°E 53.39' #6 Note: only trees to witness here.

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 1" Axle shaft 2.2 feet long with broken glass around. The centerline of East and West gravel road is 3.5 feet North and in a tree row and old pine stump fence line going South. The condition of the recorded witness are: #1 thru #4 gone, #5 and #6 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed 1" Axle shaft and set a 4" diameter Harrison cast iron monument 20" long over broken glass marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

36" White Oak South 31.26' Set spike with tag in West side of tree. #5 26" Maple S51°E 53.56' Set spike with tag in Northeast side of tree. #6 4" Maple S71°E 59.72' Set spike with tag in Northeast side of tree. 18" White Oak S27°W 15.60' Set spike with tag in West side of tree.

Signed by Norman L. Ochs Date September 8, 1997 Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Lansing, Michigan, 1975 Revised Jan., 1983



Approved by Peer Review Group on September 9, 1997

Norman L. Ochs, County Representative.

N.L.O.