

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

JAN 21 PM 3 25

For corners in

NEWAYGO

(County)

Located in:

Corner Code: #

1. Public Land Survey

T 12N R 11W

A-1

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property In Sec.

S T R

S T R

*Marlene Toogood*

VOL 001 PAGE 15

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	13	12	11	10	9	8	7	6	5	4	3	2	1
7													
8	19	18	17	16	15	14	13	12	11	10	9	8	7
9													
10	25	24	23	22	21	20	19	18	17	16	15	14	13
11													
12	31	30	29	28	27	26	25	24	23	22	21	20	19
13													

I, Norman L. Ochs in a field survey on October 26, 1993

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

NW Corner, Section 6, Croton Township.

A. Description of original monument and accessories and/or subsequent restoration:

GLO Ralph A. Smith R.L.S. #3421  
 10" B. Oak S73°W 129 lks #1 Nov. 28, 1950 1-1/2" Gas Pipe.  
 10" W. Oak N49-1/2°E 183 lks #2 W. Oak S79-1/2°E 102.7' #8  
 24" Elm N75°+ 90.8' #9  
 N.C.R.C. Sheet P. Pole N47°+W. 45.9' #10.  
 1-1/2" Pipe & stone See also Al. Meyer RLS  
 24" Tamarack N50°W 50.6' #5 L. 350, Pg. 6037  
 20" W. Oak S79°E 102.7' #6  
 24" Elm N15°E 90.6" #7

Co. Surveyor  
 Lyle Shepherds  
 Book  
 1-1/2" Gas Pipe  
 & Stone  
 18" Tamarack #3  
 N40-3/4°W 50.8'  
 W. Oak S79-1/2°E  
 102.8' #4.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1-1/2" Gas Pipe & Accepted as found.

Condition of recorded witnesses is #1 Gone, #2 Gone, #3 Gone, #4 Good Condition, #5 Gone, #6 Good Condition, #7 Gone, #8 Good Condition, #9 Gone, #10 Gone.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed 1-1/2" Gas Pipe & set 4" Dia. Harrison Cast Iron Monument and is accepted as a careful and faithful reestablishment of the position of the original corner.

36" W. Oak S79°E 103.23' (Spike in North side of tree) #4, #6, #8.  
 24" B. Oak N83°E 138.82' (Spike in South side of tree)  
 P. Pole N37°E 68.09' (PK nail in West side of Pole).  
 Top center of telephone riser S45°W 45.14'.

Signed by Norman L. Ochs  
 Norman L. Ochs  
 Surveyor's Michigan License No. 22439

Date November 8, 1993



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, REVISED BY THE BOARD, 1993

Approved by Peer Review Group Nov. 9, 1993  
 Norman L. Ochs, County Representative

SURVEY & REMONUMENTATION

JEC 07 2000

SECTION