

1993 NEWAYGO COUNTY REMONUMENTATION PROJECT  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

34 JAN 21 PM 3 25  
 Marlene Toogood

For corners in NEWAYGO (County)

|                                       | Located In:                 | Corner Code ## |
|---------------------------------------|-----------------------------|----------------|
| 1. Public Land Survey                 | T <u>12</u> N R <u>11</u> W | <u>A-2</u>     |
|                                       | T _____ R _____             | _____          |
|                                       | T _____ R _____             | _____          |
|                                       | T _____ R _____             | _____          |
| 2. Property Controlling in Section    | S _____ T _____ R _____     | _____          |
|                                       | S _____ T _____ R _____     | _____          |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____     | _____          |
|                                       | S _____ T _____ R _____     | _____          |
| 4. Lot No. _____, Recorded Plat _____ |                             |                |
| 5. Private Claims _____               |                             |                |

VOL 001 PAGE 16

Register of Deeds Stamp & File Number

I, Norman L. Ochs, in a field survey on October 26, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.


West 1/4 Corner, Sec. 6, Croton Twp.

A. Description of original monument and accessories and/or subsequent restoration:  
 GLO NCRC Sheet L.S.S. Co. Surveyor  
 8" W. Oak S70-1/2°E 354 lks. #1 18" Cherry N13°E 213.5' #3 1/4 Cor. 1/2 way on  
 10" Cherry N61°E 302 lks. #2 30" B. Oak N67°E 205.0' #4 line in 1916

Ralph A. Smith See F.B. #82, Pg. 27. 1993 Wm. Fries, Jr.  
 Nov. 29, 1950 Fd. 1-3/4" Sq. Iron & Stones  
 Iron Bar 1" x 1-1/2" Tower Leg AZ 45° 56.32' #8  
 30" B. Oak N67-1/2°E 205.0' #5 V Bolt SW Tower Leg AZ 58° 45.43' #9  
 S.E. Leg of Tower #4314 N67°+58.8' #6 X Bolt SE Tower Leg AZ 67° 58.53' #10  
 N.W. Leg of Tower #4314 N45°+56.3' #7 #12 6" Oak AZ 272° 46.83' #11  
 20" 17" 16" Tri B. Oak AZ 244° 84.99'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.  
 Found 1" x 1-1/2" Bar & accepted as found.  
 Condition of recorded witness is: #1 gone, #2 Gone, #3 Gone, #4 good condition, #5 good condition, #6 good condition, #7 good condition, #8 good condition, #9 good condition, #10 good condition, #11 gone, #12 good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Removed 1" x 1-1/2" bar and set a 4" diameter Harrison Cast Iron Monument, and is accepted as a careful and faithful reestablishment of the position of the original corner.  
 24"-24"-24" Triple B. Oak S64°W 85.03" (Spike in S side of tree) #12.  
 12" Red Pine N44°W 68.22" (Spike in SW side of tree).  
 SE Leg of Tower N67°E 58.78' (At ground) #6, #10.  
 NW leg of Tower N45°E 56.41' (At ground) #7, #8.



Signed by Norman L. Ochs  
 Surveyor's Michigan License No. 22439

Date November 8, 1993

Approved by Peer Review Group Nov. 9, 1993  
 Norman L. Ochs, County Representative

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 29, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983

SURVEY & REMONUMENTATION

JEC 07 2000

SECTION