

MAR 13 2000

SECTION

1999 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1979

00 FEB 28 PM 1 10

Form with fields: For corners in Newaygo (County), Located in: T 12N R 11W, Corner Code # H-13, 1. Public Land Survey, 2. Property Controlling in Section, 3. Miscellaneous Property in Sec., 4. Lot No., 5. Private Claims

Linda M. Brown

VOL. 2

307

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13, containing numbers 1-36.

I, Norman L. Ochs, in a field survey on July 16, 1999, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

South One Quarter Corner, Section 34, Croton Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. John Hodgson 1837 22" Pine N29°E 30 Links (18.8')#1 12" Pine N09°W 50 Links (33')#2

Lyle S. Shepherd R.L.S. #503 Witness Book Number 2, Page 109 Pine Stump N75½°E 30' #3

William Fries, Jr. R.L.S. #30389 LCRC #1320 February 3, 1998 Found ½" Iron 2 feet North of occupied centerline of the East and West road. 20" Oak N30°E 44.77' 1¼" outside diameter Pipe Hi, North One Quarter Corner, Section 3, T11N R11W, East 13.78' 6"-8" Oak Stump S55°E 52.98' 9" Oak S43°E 46.33' 18" Oak S08°W 43.57' 19" White Oak N03°W 56.54'

Patrick A. Salisbury R.L.S. #13594 February 27, 1974 Drawing Number 74011AC Set Railroad spike on approximate woods line North. 12"-10"-8" Triple Black Oak S02°E 27.07' #4 6"-8" Twin White Oak S43°E 42.59' #5 18" White Oak N23°W 58.62' #6 Set by doubling distance from the Southeast Corner to the East One Eighth line fence 1313.61 feet of Section 34.

NOTE: These witnesses were to the North One Quarter Corner of Section 3, T11N R11W

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 1" x 18" Gas Pipe in the centerline of the East and West gravel road. The condition of the recorded witnesses are: #1 thru #4 gone, #5 stump, #6 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed Gas Pipe and set a 4" diameter Harrison cast iron monument 18" long marked "County Surveyor" as a substantial marker for the quarter corner and is accepted as a careful and faithful reestablishment of the original corner.

Twin White Oak Stump S43°E 42.59' to the centerline. #5 24" White Oak N23°W 58.32' Set spike with tag #22439 in East side of tree. #6 24" Black Oak N10°E 39.40' Found spike with tag #22439 in East side of tree. 20" Red Oak S23°W 47.70' Set spike with tag #22439 in West side of tree. 14" Black Oak S31°E 38.14' Found spike with tag #22439 in Easterly side of tree. North One Quarter Corner, Section 3, T11N R11W, (Harrison monument) West 13.76'

Signed by Norman L. Ochs Date August 17, 1999

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors

Approved by Peer Review Group on October 28, 1999 Norman L. Ochs, County Representative.



Revised May 14, 1975 Revised Jan., 1983

Handwritten initials: NLO