

LAND CORNER RECORDATION CERTIFICATE VOL 001 PAGE 85
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Located In:	Corner Code #
Newaygo (County)	I-9
1. Public Land Survey	T 12N R 11W
	T _____ R _____
	T _____ R _____
	T _____ R _____
2. Property Controlling in Section	S _____ T _____ R _____
	S _____ T _____ R _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____
	S _____ T _____ R _____
4. Lot No. _____, Recorded Plat _____	
5. Private Claims _____	

NEWAYGO COUNTY
 REGISTER OF DEEDS
 MARLENE TOOGOOD

'95 MAR 14 PM 3 53

Marlene Toogood

Register of Deeds Stamp & File Number

I, Norman L. Ochs, in a field survey on September 23, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

NW Cor., Section 26, Croton Twp., Newaygo County MI

A. Description of original monument and accessories and/or subsequent restoration:

GLO John Hodgson 1837
 4" W. Oak N16QE 48 lks (31.68') #1
 4" W. Oak S31°E 77 lks (50.82') #2

Nov. 5, 1953 Ralph A. Smith RLS #3421
 Book 83, Pg. 32
 Fnd. 1/2" gas Pipe, Glass Crockery
 12" B. Oak N50°W 43.0' #3
 8" W. Oak S50°W 59.0' Gone #4.
 Measured 2646.34 ft. from the NW cor to the N-1/4 Cor. of Sec. 26.
 Measured 2643.26 ft. from the NW cor to the W-1/4 cor. of Sec. 26.

Wm. Jacques (Co. Surveyor)
 Book 1 Pg. 6 1909.
 Measured 79.16 - 1/2 chains (5224.89 ft.)
 From the SE Cor. to the SW cor. of Sec. 22 measured 40 chains (2640 ft)
 from the SE Cor. to E-1/4 cor. of Sec. 22.

(OVER)----


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

9/20/94 Fnd. 1-1/4" pipe.
 9/23/94 Set Harrison mon.
 Found 1-1/4" iron pipe and witnesses No. 1, 2 & 4 & 5 are gone, witnesses 3, 6, 7 & 8 are o.k. and measured 2644.59 from the N.W. Corner to N-1/4 corner of Section 26.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

9/23/94 Removed 1-1/4" iron Pipe & set 4" Dia. Harrison Cast Iron marker for the Section Corner, and is accepted as a careful and faithful reestablishment of the position of the original corner.

B. Oak 48" S75°E 147.07' #7 Spk. on S. side.
 B. Oak 12" S60°W 85.06' #8. Spk. on W. side.
 B. Oak 18" N10°W 61.84' #6. Spk. on E. side.
 B. Oak 18" N50°W 43.42' #3. Spk. on SW side.



Signed by Norman L. Ochs
 Surveyor's Michigan License No. 22439

Date September 28, 1994

Approved by Peer Review Group on October 19, 1994.
 Norman L. Ochs County Representative *N.L.O.*

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971
 REVISED MAY 14, 1975
 REVISED JAN. 1983

SURVEY &
 REMONUMENTATION

JEC 07 2000

SECTION

A. cont.

Dec. 1974 Clinton E. Cole RLS #17615
LCRC #350
Found 1-1/4" Pipe
18" B. Oak N10°W 61.88' #6
18" B. Oak N50°W 43.39' #3
12" W. Oak S48°W 52.80' #5

Measured 2644.76 ft. from the NW cor.
to the N-1/4 cor. of Sec. 26. Measured
2641.20 ft. from the NW cor. to the W-1/4
cor. of Sec. 27.

June 16, 1990 Glen S. Hackbardt RLS #25844
Recorded in Liber 351 Pg. 4196.
1" Pipe
18" Oak S45°W 52.8' #5.
36" Oak S75°E 147.05' #7
10" Oak S60°W 85.05' #8
Measured 2644.68 ft. from the NW cor.
to the N-1/4 cor. of Sec. 26.

April 3, 1989 Newaygo Eng. &
Survey Co. Job #89046B&M
12" W. Oak S48°W 52.80' #5
18" B. Oak N10°W 61.88' #6
18" B. Oak N50°W 31.50'
Measured 2604.06 ft. from the
NE cor. to the N-1/4 cor. of
Sec. 27.

SURVEY &
REMONUMENTATION

DEC 07 2000

SECTION