

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

VOL 001 PAGE 86

For corners in

Newaygo (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>12N</u> R <u>11W</u>	J-9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

NEWAYGO COUNTY
REGISTER OF DEEDS
MARLENE TOOGOOD
'95 MAR 14 PM 3 53
Marlene Toogood
Register of Deeds Stamp & File Number

I, Norman L. Ochs, in a field survey on September 24, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.
N-1/4 Corner, Section 26, Croton Twp., Newaygo Co. MI


A. Description of original monument and accessories and/or subsequent restoration:

GLO John Hodgson 1837 Nov. 5, 1953 Ralph A. Smith RLS #3421
Book 83 Pg. 32
8" Aspen N45°W 30 lks (19.80') #1
1" Gas Pipe & Crockery. 8" B. Oak S05°W
4" Pine SW 84' #3 44.8' #5
4" B. Oak S76°E 58 lks (38.28') #2
8" Pine South 105' #4
3" W. Oak N55°E 13.25' #6
Lyle S. Shepherd RLS #503
Book 49, Pg. 74 1928
Measured 2684.50 ft. from the
N-1/4 cor. to the NE cor. of Sec. 26. Measured 2646.34 ft. from the N-1/4 cor. to the
NW cor. of Sec. 26 and measured 2700.46
ft. from the N-1/4 cor. to the NE
corner of Sec. 26. (See back)--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
9/24/94 Found 1/2" gal. pipe and witnesses.
No. 1, 2, 3, 4 & 7 are gone but witnesses 5, 6, 8 & 9 are still ok. and
measured 2644.59 from N-1/4 to NW corner and measured 2684.19 from N-1/4 to NE
corner of Sec. 26.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Fnd. 1/2" gal. pipe, removed and set 4" diameter Harrison cast iron monument 20" long and accepted as a careful and faithful reestablishment of the original corner.
9" W. Oak N60°E 13.18' #6 Blass cap & spike on SE side.
12" W. Pine N20°W 35.15' #9 Spk. on W. side.
18" B. Oak S10°W 44.54' #5 Spk. on SE side.
P Pole S30°E 65.22' Spk. on E. side. #8.



Signed by Norman L. Ochs
Norman L. Ochs 22439
Surveyor's Michigan License No.

Date September 28, 1994.

Approved by peer review group on October 19, 1994.
Norman L. Ochs, County Representative

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

SURVEY &
REMONUMENTATION

DEC 07 2000

SECTION

A. cont.
Dec. 1974, Clinton E Cole RLS #17615
LCRC #350
Fnd. 1/2" galvanized Pipe
6" W. Oak N60°E 13.25' (O.B.T.) #6
10" B. Oak S10°W 44.80' (O.B.T.) #5
12" W. Pine S70°E 100.91' #7

Measured 2644.76 ft. from the N-1/4 cor. to the NW cor. Measured 2694.51 ft. from the N-1/4 cor. to the C-1/4 cor. Measured 2684.26 ft. from the N-1/4 cor. to the NE cor. all in Sec. 26.

June 11, 1991 Burt Wickham Jr. RLS #17639
Recorded in Liber 352 Pg. 6195

Measured 2598.34 ft. from the S-1/4 cor. to the C-1/4 cor. of Sec. 23. Measured 2684.04 ft. from the S-1/4 cor. to the SE cor. of Sec. 23.

June 16, 1990 Glen S. Hackbardt
RLS #25844
Recorded in Liber 351, Pg. 4196
1/2" Pipe
C.P. S30°E 65.2' #8
10" Pine N20°W 35.15' #9
15" Oak S10°W 44.5' #5

Measured 2644.68 ft. from the N-1/4 cor. to the NW cor. and measured 2684.18 ft. from the N-1/4 cor. to the NE cor. all in Section 26.

SURVEY &
REMONUMENTATION

JEC 07 2000

SECTION