

**SURVEY &
REMONUMENTATION**

APR 24 1995 1994 NEWAYGO COUNTY REMONUMENTATION PROJECT

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

VOL. **001** PAGE **87**

NEWAYGO COUNTY
REGISTER OF DEEDS
MARLENE TOOGOOD

'95 MAR 14 PM 3 53

Marlene Toogood

Register of Deeds Stamp & File Number

For corners in

Newaygo
(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>12N</u> R <u>11W</u>	<u>K-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

I, Norman L. Ochs, in a field survey on September 9, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

NE corner, Section 26, Croton Twp., Newaygo County MI

A. Description of original monument and accessories and/or subsequent restoration:

- GLO John Hodgson 1837 Nov. 4, 1953 Ralph A. Smith RLS #3421
- 8" Aspen N18°E 18 lks (57.42') #1 1-1/4" Well Point w/broken glass book 83 pg 3
- 6" Aspen S20°E 94 lks (62.04') #2 30" W. Oak S66-1/4°E 51.7' #3
- 12" B. Oak S55°W 73.5' #4

Ralph A. Smith RLS #3421 Measured 2685.63 ft. from the NE cor. to the N-1/4 cor. of Sec. 26. Measured 2646.34 ft from the NW cor. to the N-1/4 cor. of Sec. 26.

Book Unknown Pg. 85
24" W. Oak S66-1/4°E 52.2' #3
1928 Lyle S. Shepherd RLS #503
Book 49 Pg. 74

Measured 2671.50 ft. from the NE


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

cor. to the E-1/4 cor. of Sec. 26 and measured 2684.50 ft. from the NE cor. to the N-1/4 cor. of Sec. 26

9/9/94 Newaygo Eng. & Survey Co. Found 1-1/4" iron pipe 9" long on top of a 1-1/4" well point and witnesses 1 thru 5 & No. 9 & No. 11 to be gone but found witnesses 6, 7, 8 and 10 to be OK. We measured 2684.19 ft. from NE cor. to N-1/4 Cor. of Sec. 26.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted the well point to be in proper position and placed a 4" Harrison cast iron monument 20" long on top of well point and accepted as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.



(See back) --

Signed by Norman L. Ochs
Norman L. Ochs 22439

Date September 9, 1994

Surveyor's Michigan License No. _____
Approved by Peer Review Group on October 19, 1994
Norman L. Ochs, County Representative

APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1994
REVISED MAY 14, 1994
REVISED JAN. 1, 1994

NO

A. cont.

Ralph A. Smith RLS #3421
Book 83, Pg. 68 1957
1/2" Gas Pipe
12" B. Oak S55°W 73.8' #4
30" R. Oak S55°E 52.5' #3

New. Eng. & Survey Co. 9/8/72

Recorded in Series F No. 9517
Recorded in Series G No. 251 6/28/74
30" R. Oak S53°E 53.62' #3
12" B. Oak S53°W 74.40' #4
7" W. Oak S20°W 54.70' #5

Measured 2652.59 ft. from the SW
cor. to the S-1/4 cor. of Sec. 24
and measured 2635.89 ft. from the SW
cor. to the S-1/4 cor. of Sec. 24.

May 20, 1988 Newaygo Eng. & Sur. Co.

Job No. 88052B 1-1/4" Pipe
12" W. Oak N17°E 96.63' #6
8" Tw. W. Oak S49°E 96.08' #7
P. Pole S40°W 77.24' #8
8"-10" Tw. W. Oak S75°W 100.64' #9
Measured 2652.29 ft. from the NW cor.
to the N-1/4 cor. of Sec. 25 and
measured 2672.80 ft. from the NW cor.
to the W-1/4 cor. of Sec. 26.

June 16, 1990 Glen S. Hackbardt RLS#25844
Recorded in Liber 351 Pg. 4196 1-1/4" Pipe

C.P. N30°W 60.6' #10
8" Oak S45°E 36' #11
C.P. S40°W 77.25' #8
Measured 2684.18 ft. from the NE cor.
to the N-1/4 cor. of Sec. 26.

June 5, 1991 Burt Wickham Jr RLS#17639

Recorded in Liber 352 Pg. 6195
Measured 2684.04 ft. from the SE cor. to
the S-1/4 cor. of Sec. 23.

C cont.

9/24/94 9/24/94 Newaygo Eng. & Survey
End. 1-1/4" Pipe on top of 1-1/4" well
point. Set 4" dia. Harrison cast iron
mon. 20" long.

14" W. Oak N21°E 96.64' Spk. on W side #6
P.P. S43°W Spk. on NW side 77.27' #8
P.P. N27°W Spk. on E side 60.63' #10
9" Oak S44°E Spk. on SW side 95.98' #7

NCRC Sheet

1" Pipe
30" R. Oak S53°E 52.5' #3
12" B. Oak S53°W 73.8' #4

Nov. 6, 1985 Wm. Fries Jr RLS #30389
LCRC #645

End. 1-1/4" Pipe
14" W. Oak AZ 17° 96.63' #6
8" Tw W. Oak AZ 131° 96.08 #7
P. Pole AZ 220° 77.24' #8
8" & 10" Tw. W Oak AZ 255° 100.64' #9

1974 Clinton E. Cole RLS #17615

Measured 2671.70 ft. from the NE cor.
to the E-1/4 cor. of Sec. 26 and measured
2684.26 ft. from the NE cor. to the N-1/4
of Sec. 26.

May 8, 1992 James J. Keller RLS #10693

Recorded in Liber 354 Pg 1348 thru 1351
1/2" Pipe
14" W. Oak N21°E 96.65' #6
9" Oak S44°E 95.99' #7
P. Pole S43°W 77.31' #8
P. Pole N27°W 60.65' #10
Measured 2643.80 ft. from the SW cor.
to the S-1/4 cor. of Sec. 24 and meas-
ured 2635.38 ft. from the SW cor. to the
W-1/4 cor. of Sec. 24.