

SURVEY & REMONUMENTATION

MAR 19 1998

1997 Newaygo County Remonumentation Project

NEWAYGO COUNTY
REGISTER OF DEEDS
LINDA M. BROWN

SECTION

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT of Act 74, Mich. P.A. 1970

'98 MAR 6 PM 12 35

Linda M. Brown

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>12N</u> R <u>11W</u> T <u>13N</u> R <u>11W</u> T ___ R ___ T ___ R ___	<u>M-1</u> ✓ <u>M-13</u> _____ _____
2. Property Controlling in Section	S ___ T ___ R ___ S ___ T ___ R ___	_____ _____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___ S ___ T ___ R ___	_____ _____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

VOL. 2

83

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Norman L. Ochs, in a field survey on August 4, 1997, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Northeast Corner, Section 1, Croton Township, Newaygo County, Michigan.
Southeast Corner, Section 36, Big Prairie Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. John Hodgson 1837
14" Pine S42½°W 143 Links (94.38') #1
12" Pine N16¾°E 150 Links (99') #2

Lyle Shepherd's Book Number 2 Page 107
Sleigh Shoe and Crockery
18" Black Oak S59¼°W 50' #4
6" White Pine N34°W 77.1' #5

U.S.F.S. Information and Mecosta County Road
Commission Sleigh Shoe
30" Black Oak N30°W 66.3' #3
30" Black Oak S50°W 50.0' #4

OVER ↗

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found P.K. nail in center of 1½" Pipe over 1½" X 22" Iron pipe over sleigh shoe with crockery in the centerline of North and South road and the centerline of road going East is 2.5 feet South. The condition of the recorded witnesses are: #1 thru #3 gone, #4 stump, #5 and #6 gone, #7 stump, #8 gone, #9 good condition, #10 and #11 gone, #12 good condition, #13 gone, #14 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed Iron pipes and set a 4" diameter Harrison cast iron monument 20" long on top of sleigh shoe and crockery marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

30" Black Oak Stump S65°W 50.59' Found nail with bottle cap on Southeast side of stump. #4
32" Oak Stump N75°W 75.15' to face. #7
¾" Pipe with cap inside (#12679) N85°W 33.10' #9
18" Red Oak S71°W 76.00' Found nail in root in South side of tree. #12
Power Pole N21°W 124.36' Found nail in Northeast side of pole. #14
14" Black Oak N48°W 59.45' Found P.K. nail in Northeast side of tree.
Power Pole S54°E 107.32' Set P.K. nail in Northeast side of tree.



Signed by Norman L. Ochs Date September 8, 1997
Norman L. Ochs

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Revised May 14, 1975
Revised Jan., 1983

Approved by Peer Review Group on October 14, 1997
Norman L. Ochs, County Representative.

N. L. O.