

1993 NEWAYGO COUNTY REMONUMENTATION PROJECT

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

JAN 21 PM 3 25

Marlene Toogood

VOL 001 PAGE 10

Register of Deeds Stamp & File Number

For corners in

Newaygo (County)	Located In:	Corner Code ##
1. Public Land Survey	T <u>12N</u> R <u>14W</u>	C-3
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

I, Norman L. Ochs, in a field survey on December 15, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. SE Corner, Section 6, Sheridan Township
Description of original monument and accessories and/or subsequent restoration:

G.L.O. John Mullett 1837
18" Beech S47°W 25 LKS (16.5') #1
12" Beech S43°E 17 LKS (11.22') #2

Lyle S. Shepherd #503
Field Book 84 Pg. 29
1950
2" Gas pipe, glass & stone
T.Pole N50°W 38.8' #3
P.Pole S45°E 66.5' #4

1955 Ralph A. Smith #3421
Found Gas Pipe
T.Pole N140°W 48.6' #5
P.Pole S41°E 66.5' #4
6" Apple S57°W 69.8' #6

April 2, 1891 John C. Brewster
Gas pipe 2 feet long
Book A PG. 125

NCRC SHEET
Gas pipe
T.Pole N40°W 48.6' #5
P.Pole S41°E 66.5' #4

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: *continued on other side.
12-15-93


Found 1" Iron Pipe & replaced with 4" Harrison Cast Iron Monument.

Condition of recorded witnesses is: #1 thru #6 Gone, #7 thru #10 Good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted 4" Harrison Cast Iron Monument as a substantial marker for the section corner and is accepted as a careful and faithful re-establishment of the original corner.

P.Pole S76°E 45.10' #7
10" Tri Cedar AZ 133° 174.85 #8
Iron and Cap AZ 314° 46.92' #9
Tel. Pedestal #5599 AZ 319° 48.21' #10



Signed by Norman L. Ochs

Date December 28, 1993

Norman L. Ochs 22439

Approved by Peer Review Group on December 29, 1993

Norman L. Ochs, County Representative

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

SURVEY &
REMONUMENTATION

JEC 07 2000

SECTION

Continuation of Section 7A.

6" Apple S 57°W 69.8' #6	1993 William Fries Jr. #30389
	FD 1" Pipe
Sept. 19 51 1978	P.Pole AZ 98° 45.01' #7
New. Eng. & Sur. Co.	10" Tri Cedar AZ 133° 174.85' #8
3/4" Pipe	Iron & Cap AZ 314° 46.92' #9
P.Pole N34°W 49.14' #5	Tel Pedestal #5599 AZ 319° 48.21' #10
P.Pole S76°E 45.10' #7	LCRC #1138
12" Apple S 61°W 69.52' #6	

Continuation of Section B.

In 1891 John C. Brewster found 2 foot long Gas pipe. He measured 39.81 CH (2627.46 ft) from the SE corner to the E $\frac{1}{4}$ corner of said section in 1950. Lyle S. Shepherd broke section 6. He found a 2" Gas pipe with Glass & Stone. Shepherd measured 2623.00 ft from the SE corner to the E $\frac{1}{4}$ corner and measured 2630.0 ft from the SE corner to the S $\frac{1}{4}$ corner of said section. In 1955 Ralph A. Smith found a Gas Pipe. Smith measured 2629.2 ft from the NW corner of section 8 to the W $\frac{1}{4}$ corner of section 8. In 1965 Ralph A. Smith measured 2626.10 ft from the SW corner (common corner) to the W $\frac{1}{4}$ corner of section 5. In 1978 New. Eng. & Survey found a 3/4" pipe. They measured 2625.42' from the SE corner of sec. 6 to the E $\frac{1}{4}$ corner of section 6 and measured 2628.53 ft from the SE corner to the S $\frac{1}{4}$ corner of section 6. In 1991 William Fries Jr. found a 1" OD Pipe, 5 ft North of fence to East and 5 ft North of occupied centerline of road to West.

SURVEY &
REMONUMENTATION

DEC 07 2000

SECTION