

SURVEY & REMONUMENTATION

MAY 28 1997

COMMISSION

1996 Newaygo County Remonumentation Project

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT of Act 74, Mich. P.A. 1970

NEWAYGO COUNTY
REGISTER OF DEEDS
LINDA M. BROWN

'97 FEB 12 PM 4 45

Linda M. Brown

For corners in Newaygo (County) Located in: Corner Code #

1. Public Land Survey T 12N R 14W C-6
T ___ R ___
T ___ R ___
T ___ R ___

2. Property Controlling in Section S ___ T ___ R ___
S ___ T ___ R ___

3. Miscellaneous Property in Sec. S ___ T ___ R ___
S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

VOL. 1 PAGE 232

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

I, Norman L. Ochs, in a field survey on October 3, 1996, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

West One Quarter Corner, Section 17, Sheridan Township, Newaygo County, Michigan

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. John H. Mullett 1838
10" Black Ash S36°W 11 Links (7.26') #1
6" Black Ash N67°E 19 Links (12.54') #2

Patrick A. Salisbury R.L.S. #13594
Set 1" Pipe ±24" long half way and on line between the Northwest and Southwest Section Corners. February 6, 1975
28" Maple S63°W 48.87' #3
Wood Corner Fence Post N40°E 42.34' #4
10" Maple S45°E 54.14' #5
30" Maple N27°W 43.53' #6

Douglas W. Bonnema R.L.S. #12579
Found 1" Iron November 9, 1976
12" Maple Southeast 54.37' #5
Fence Post Northeast 42.25' #4
36" Maple North Northwest 43.28' #6

William Fries, Jr. R.L.S. #30389
January 20, 1986 LCRC #708
Found 1 1/4" Outside diameter pipe which fits record accessories. Pipe was bent so I reset it with 1/2" Iron and cap
14"-14" Twin Red Maple N69°E 35.05' #7
15" Red Maple S48°E 54.32' #5
35" Red Maple S61°W 48.92' #3
12" Red Maple N88°W 26.65' #8

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 1/2" Rod and cap #30389 in centerline of road going South and the centerline of road going North is 6 feet East and the centerline of road going East is 3 ft North and the condition of the recorded witnesses are: #1 and #2 gone, #3 good condition, #4 (fallen), #5 thru #7 good condition, #8 gone.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:


Removed 1/2" Rod and cap #30389 and set a 4" diameter Harrison cast iron monument 20" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

28" Maple S63°W 48.92' Set spike with tag over existing spike in Northwest side of tree. #3
10" Maple S45°E 54.71' Found spike in Southwest side of tree. #5
36" Maple N27°W 43.21' Found spike in Southwest side of tree. #6
14"-14" Twin Red Maple N69°E 35.18' Spike in Southeast side of tree. #7
14" Maple N75°W 27.34' Tree has been previously blazed.

Signed by Norman L. Ochs Date October 17, 1996

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1997
Revised May 12, 1978
Revised Jan., 1963



Approved by Peer Review Group On October 24, 1996
Norman L. Ochs, County Representative.

N.L.O.