

SURVEY & REMONUMENTATION

MAR 02 1999

1998 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

'99 FEB 17 PM 3 33

SECTION LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

Linda M. Brown

For corners in Newaygo (County) Located in: Corner Code #

1. Public Land Survey T 12N R 14W F-1
 T ___ R ___
 T ___ R ___
 T ___ R ___

2. Property Controlling in Section S ___ T ___ R ___
 S ___ T ___ R ___

3. Miscellaneous Property in Sec. S ___ T ___ R ___
 S ___ T ___ R ___

VOL. 2

168

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Norman L. Ochs, in a field survey on May 13, 1998, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

North One Quarter Corner, Section 4, Sheridan Township, Newaygo County, Michigan.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Not set. Lyle S. Shepherd R.L.S. #503
 Book 81C Page 16 January 17, 1947
 Iron in Monument Box in pavement.

Newaygo County Road Commission Sheet
 1" Iron Monument Box
 8" Locust N40°W 43.6' #1
 30" Elm South 27.6' #2
 Patrick A. Salisbury R.L.S. #13594
 December 18, 1972 Drawing Number 72165P
 1" Iron in monument box
 8" Locust N40°W 43.6' #1
 30" Elm South 27.6' #2

Patrick A. Salisbury R.L.S. #13594
 Plat of "Fremont Farms". The Point of Beginning and the Northwest Corner of said plat is 626.71 feet East of the North One Quarter Corner of Section 4.
 April 3, 1975 Recorded in Liber 10 of plats, Pages 6 thru 8

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 1 1/2" X 35" Shaft in monument box on line ± with a brush and tree row going South and the centerline of the East and West bituminous road is 2 feet North. The condition of the recorded witnesses are: #1 and #2 gone.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed Shaft and monument box and set a 2 3/4" X 20" Harrison cast iron monument marked "County Survey" in new 8" diameter monument box as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

1/2" Rerod with cap #30389 N18°W 52.40'
 Power Pole N37°W 63.40' Found P.K. nail with tag #22439 in Easterly side of pole.
 1/2" Rerod South 50.00'
 Power Pole S10°W 44.40' Found P.K. nail with tag "Advanced Survey & Map" in West side of pole.
 South One Quarter Corner, Section 33, T13N R14W (2 3/4" X 20" Harrison cast iron monument in monument box)
 West 16.65'

Signed by *Norman L. Ochs* Date October 15, 1998
 Norman L. Ochs

Surveyor's Michigan License No. 22439

Form approved by Michigan Board of Land Surveyors, Jan 28, 1971
 Revised May 14, 1975
 Revised Jan., 1983

Approved by Peer Review Group on October 22, 1998
 Norman L. Ochs, County Representative.

N.L.O.

