

MAR 18 2000

SECTION

1999 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

00 FEB 28 PM 1 10

For corners in Newaygo (County) Located in: Corner Code # 1. Public Land Survey T 12N R 14W H-13 2. Property Controlling in Section S T R 3. Miscellaneous Property in Sec. S T R 4. Lot No. , Recorded Plat 5. Private Claims

Linda M. Brown

VOL. 2

312

Register of Deeds Stamp & File Number

Grid table with columns A-L and rows 1-13. Cell (12, 34) contains a small circle.

I, Norman L. Ochs, in a field survey on August 9, 1999, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

South One Quarter Corner, Section 34, Sheridan Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Mullett and Brookfield 1837 8" Black Ash N34°E 15 Links (9.90') #1 8" Birch N39°W 16 Links (10.56') #2

Norman L. Ochs R.L.S. #22439 January 20, 1999 Set 1/2" Rod and cap Set half way and on line between the Southeast and the Southwest Corners of Section 34 in the centerline of a two-track running East and West. No evidence of fences or other occupation found.

Donald G. Sandel R.L.S. #25870 February 23, 1999 Recorded in Liber 374, Page 1069 Found capped iron #22439 8" Poplar N40°E 10.47' #3 12" Poplar S22°E 31.99' #4 13" Poplar S44°W 31.20' #5 14" Poplar N68°W 25.23' #6

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 1/2" Rod and cap #22439 in centerline of the East and West two-track. No apparent occupation North or South. The condition of the recorded witnesses are: #1 and #2 gone, #3 thru #6 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed 1/2" Rod and cap #22439 and set a 4" diameter Harrison cast iron monument 20" long marked "County Surveyor" as a substantial marker for the quarter corner and is accepted as a careful and faithful reestablishment of the original corner.

8" Maple S47°E 28.06' Set spike with tag #22439 in Northerly side of tree. 8" Maple S03°W 36.72' Set spike with tag #22439 in West side of tree. 10" Elm S53°W 35.21' Set spike with tag #22439 in Northwesterly side of tree. 4"-4" Twin Maple N08°W 52.13' Set spike with tag #22439 in East side of tree. North One Quarter Corner, Section 3, T11N R14W, (Harrison Monument) West 16.50'

Signed by Norman L. Ochs Date August 17, 1999

Surveyor's Michigan License No. 22439 Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Approved by Peer Review Group on October 28, 1999 Norman L. Ochs, County Representative.

Revised May 14, 1975 Revised Jan., 1983

N.L.O.

