

MAR 02 1999

1998 Newaygo County Remonumentation Project LINDA M. BROWN

NEWAYGO COUNTY REGISTER OF DEEDS

SECTION

LAND CORNER RECORDATION CERTIFICATE 99 FEB 17 PM 3 36
FILING REQUIREMENT of Act 74, Mich. P.A. 1970

For corners in Newaygo (County) Located in: Corner Code #

1. Public Land Survey T 12N R 14W K-4
T ___ R ___
T ___ R ___
T ___ R ___

2. Property Controlling in Section S ___ T ___ R ___
S ___ T ___ R ___

3. Miscellaneous Property in Sec. S ___ T ___ R ___
S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Linda M. Brown

VOL. 2

181

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Norman L. Ochs, in a field survey on June 24, 1998, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

East One Quarter Corner, Section 11, Sheridan Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. John Mullett 1838
18" Beech N62°E 17 Links (11.22') #1
8" Beech S24°W 17 Links (11.22') #2

Delos G. Anderson (County Surveyor)
Book A Pages 161 and 162 March 30, 1895
Wagon Hub Iron Stake 24" long

Newaygo County Road Commission Sheet
Monument Box in pavement

William M. Jacques (County Surveyor)
Book B Pages 42 and 43 April 22, 1910
Iron Hub and Axle with broken glass around.

William Fries, Jr. R.L.S. #30389
LCRC #900 February 22, 1989
Found 1" Iron in a Monument Box 1 foot West of the occupied centerline of a North and South road and in a tree row to the West and East.
30" Basswood N43°E 68.76' #3
3 1/2" X 5 1/2" Sign Post S88°E 69.01' #4
Power Pole S48°W 69.32' #5
Concrete Monument with cap #30389 West 50.10' #6

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 1" X 24" Rod, Wagon Hub with 2 1/2" diameter top (3 3/4" diameter bottom and 12" long) and broken glass in monument box. The centerline of the North and South bituminous road is 1 foot ± East and on line ± with East and West tree \ brush row. The condition of the recorded witnesses are: #1 and #2 gone, #3 thru #6 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed Rod, Wagon Hub, broken glass and set a 2 3/4" X 20" Harrison cast iron monument marked "County Survey" in new 8" diameter monument box as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

36" Ash N48°E 68.93' Found nail with tag "Advanced Survey & Map", set new spike with tag #22439 in West side of tree. #3
4" X 6" Sign Post S86°E 69.07' Found P.K. nail with tag "Advanced Survey & Map" in North side of post. #4
Power Pole S50°W 69.18' Found P.K. nail with tag "Advanced Survey & Map" in Northwesterly side of pole. #5
3" diameter concrete monument West 49.97' with cap #30389. #6
Power Pole S83°E 45.53' Set spike with tag #22439 in South side of pole.

Signed by Norman L. Ochs

Date October 15, 1998

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 23, 1973

Approved by Peer Review Group on October 22, 1998

Norman L. Ochs, County Representative.

N.L.O.

