

MAR 02 1999

NEWAYGO COUNTY
REGISTER OF DEEDS
LINDA M. BROWN

1998 Newaygo County Remonumentation

'99 FEB 17 PM 3 37

SECTION

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT of Act 74, Mich. P.A. 1970

Linda M. Brown

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>12N</u> R <u>14W</u>	<u>K-13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

VOL. 2 188

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on January 7, 1998, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Southeast Corner, Section 35, Sheridan Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

- | | |
|--|--|
| G.L.O. Mullett and Brookfield 1838
10" Beech N31°E 42 Links (27.72') #1
18" Beech N24°W 48 Links (31.68') #2 | Patrick A. Salisbury R.L.S. #13594
December 14, 1971 Found 1" Rod
Telephone Pole S40°W 85.86' #5
Northeast Corner School Foundation S40°E 99.15' #3
18" Twin Maple South 52.61' #4
Northeast Corner, Section 2, T11N R14W, East 32.90' #6 |
| Newaygo County Road Commission Sheet
Iron 1969
Northeast Corner School Foundation S40°E 98.8' #3
8" Twin Maple South 52.6' #4 | |

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 1" Rod 2 feet long and 1/2" Rod 18" long. The centerline of the North and South bituminous road is 10 feet East and the centerline of bituminous road going West is 3 feet South and the centerline of gravel road going East is 3 feet South and the condition of the recorded witnesses are: #1 thru #5 gone, #6 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed both Rods and set a 2 3/4" diameter Harrison cast iron monument 20" long marked "County Survey" in monument box as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

- Northeast Corner, Section 2, T11N R14W, East 33.00' #6
- Power Pole N48°W 105.75' Found spike in Northeast side of pole.
- 16" Ash S50°E 66.00' Found spike in Northeast side of tree.
- Northwest Corner School Foundation S30°E 93.21'
- 10" to 5" Clump Maple S81°W 146.50' Set spike and tag in side of tree.

Signed by Norman L. Ochs Date November 5, 1998

Surveyor's Michigan License No. 22439 Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Approved by Peer Review Group on December 22, 1998
Norman L. Ochs, County Representative.

N.L.O.

Revised May 14, 1975
Revised Jan., 1983

