

1993

1993 NEWAYGO COUNTY REMONUMENTATION PROJECT

LEWIS COUNTY  
REGISTER OF DEEDS  
MARLENE TOOGOOD

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

94 JAN 21 PM 3 26

For corners in

NEWAYGO

(County)

Located In:

Corner Code #:

- 1. Public Land Survey T 13N R 11W A-1
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

*Marlene Toogood*

VOL 001 PAGE 33

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

|    |    |    |    |    |    |    |   |   |   |   |   |   |   |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

I, Norman L. Ochs, in a field survey on November 5, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

N.W. Corner, Sec. 6, Big Prairie Twp., Newaygo County, MI

A. Description of original monument and accessories and/or subsequent restoration.

- G.L.O. J. Hodgson 1837 NCRC Sheet 1988 Wm. Byl, Inc.
- 8" W. Oak N54°W 38 lks #1 R.R. Rail Iron Pipe
- 14" Maple S40°E 14 lks #2 6" B. Oak N48°W 75.05' #7 6" B. Oak N48°W 75.05' #13
- 1916 & Fnd. R.R. Iron (3&4) 8" Maple N81°E 156.5' #8 8" Maple N81°E 157.30' #14
- 10-05-34 Lyle S. Shepherd C.P. Tower S37°E 57.25' #9 C.P. Tower S37°E 57.34' #15
- 16" Pine Stp. N38-1/2°E 76' #3 1973 New Eng. & Sur Co Re-bar
- W. Oak N48-1/2°E 54' #4 1934 6" B. Oak N48°W 75.05' #10
- NW Tower Leg SW 57' #5 8" Maple N81°E 156.5' #11
- 4" Oak SW 51.7' #6 CP Tower S31°E 57.25' #12

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

Found 1/2" Pipe & 1/2" rod. & R.R. Rail

Condition of recorded witnesses is: #1 gone, #2 gone, #3 gone, #4 gone, #5 good condition, #6 gone, #7 good condition, #8 gone, #9 good condition, #10 good condition, #11 gone, #12 good condition, #13 good condition. #14 gone, #15 good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set cast <sup>Iron</sup> Harrison Mon. and is accepted as a substantial marker for the Section corner, and is accepted as a careful and faithful reestablishment of the position of the original corner.

- N.W. Leg of Tower at ground S37°E 57.38' #5, #9, #12, #15, #20.
- 18" B. Oak N48°W 75.00' (Nail in East side of tree) #7, #10, #13,
- 26" Forked B. Oak N67°W 91.55' (Spike in South side of tree).
- 15" W. Oak 107.60' (Spike in NW side of tree).



Signed by Norman L. Ochs  
Surveyor's Michigan License No. 22439

Date November 8, 1993

Approved by Peer Review Group November 9, 1993  
Norman L. Ochs, County Representative