

SURVEY & REMONUMENTATION

MAR 02 1999

1998 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT of Act 74, Mich. P.A. 1970

FEB 17 PM 3 39

SECTION

For corners in Newaygo (County) Located in: _____ Corner Code # _____

1. Public Land Survey T 13N R 11W B-1
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Linda M. Brown

VOL. 2

232

Register of Deeds Stamp & File Number

	A	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5		4		3		2		1		
3												
4	7	8		9		10		11		12		
5												
6	18	17		16		15		14		13		
7												
8	19	20		21		22		23		24		
9												
10	30	29		28		27		26		25		
11												
12	31	32		33		34		35		36		
13												

I, Norman L. Ochs, in a field survey on October 22, 1998, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

North One Quarter Corner, Section 6, Big Prairie Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Not set. Norman L. Ochs R.L.S. #22439
Drawing Number 98082AC April 29, 1998
Lionel Roy Emery R.L.S. #24593 Found 1/2" Rod and cap (illegible)
May 29, 1981 LCRC #527 6" Maple N03°W 41.25' #5
Found 1/2" Iron Rod with plastic cap (illegible) 12" Red Oak S19°W 47.30' #6
Concrete Monument N30°E 37.44' #1 Power Pole S60°E 77.50' #7
1/2" Iron Rod East 17.48' #2 4" Concrete Monument N30°E 37.40' #1
10" Poplar S55°E 52.46' #3
12" Poplar S08°E 25.05' #4

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 1/2" X 18" Rerod and the centerline of the East and West bituminous road is 1 foot North and the centerline of the two-track going South is 14 feet ± West. The condition of the recorded witnesses are: #1 and #2 good condition, #3 and #4 gone, #5 thru #7 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed Rerod and set a 2 3/4" X 20" Harrison cast iron monument marked "County Survey" in new 8" diameter monument box as a substantial marker for the section corner and is accepted as a careful and faithful establishment of the best available position of the corner.

3" diameter Concrete Monument with 1/2" Rerod N25°E 37.50' #1
South One Quarter Corner, Section 31, T14N R11W, East 17.45' #2
6" Maple N08°W 41.26' Found spike with tag #22439 in Easterly side of tree. #5
14" Red Oak (blazed) S15°W 47.27' Found spike with tag #22439 in West side of tree. #6
Power Pole S64°E 77.68' Found spike with tag #22439 in Northeasterly side of pole. #7

Signed by Norman L. Ochs Date November 3, 1998
Norman L. Ochs

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Approved by Peer Review Group on December 8, 1998
Norman L. Ochs, County Representative.

Revised May 14, 1975
Revised Jan., 1983



N.L.O.