

**SURVEY &  
REMONUMENTATION**

APR 24 1995 1994 NEWAYGO COUNTY REMONUMENTATION PROJECT

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

VOL **001** PAGE **98**

For corners in

<u>Newaygo</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>13N</u> R <u>11W</u>	<u>B-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

NEWAYGO COUNTY  
REGISTER OF DEEDS  
MARLENE TOOGOOD

'95 MAR 14 PM 3 54

*Marlene Toogood*

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Norman L. Ochs, in a field survey on November 29, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9	●												
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

N. 1/4 Corner, Section 30, Big Prairie Twp., Newaygo Co., MI

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. James H. Mullett 1838  
12" W. Oak S26°E 14 lks. (9.24') #1  
12" B. Oak S69°E 40 lks. (26.40') #2

Newaygo Engineering and Survey Co. March 31, 1993  
Measured 5383.95 fet from the N.W. Corner to the N.E. Cor. of Sec. 30.


William Fries Jr. P.S. #30389 L.C.R.C. 1205 November 11, 1993  
Set iron and cap in intersection of fences North-South-West and East, corner is 115 feet South of P.I. in power line.  
P.Pole N07°E 115.72' #3  
8" W. Pine S50°E 52.28' #4  
8" R. Oak S03°E 59.64' #5  
11" W. Oak S27°W 40.99' #6

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Found 1/2" Iron and cap in intersection of fences North-South-West and East, corner is 115 feet South of P.I. in power line.

Measured 2729.9 feet from the N. 1/4 Corner to the N.W. Corner of Sec. 30 and measured 2653.9 feet from the N. 1/4 Corner to the N.E. Corner of Sec. 30.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Removed 1/2" Iron and cap and set a 4" dia. Harrison Cast Iron Monument 20" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the position of the original corner.

P.I. P. Pole N07°E 115.72' #3  
8" W. Pine S50°E 52.28' #4  
8" R. Pine S03°E 59.64' #5  
11" W. Oak S27°W 40.99' #6



Signed by Norman L. Ochs

Date November 30, 1994

Surveyor's Michigan License No. #22439

Approved by Peer Review Group on December 1, 1994  
Norman L. Ochs, County Representative. *n.l.o.*