

SURVEY & REMONUMENTATION

1998 Newaygo County Remonumentation Project

NEWAYGO COUNTY
REGISTER OF DEEDS
LINDA M. BROWN

MAR 02 1999

LAND CORNER RECORDATION CERTIFICATE '99 FEB 17 PM 3 39
FILING REQUIREMENT of Act 74, Mich. P.A. 1970

Linda M. Brown

SECTION

For corners in _____
Newaygo _____
(County)

Located in: _____ Corner Code # _____

1. Public Land Survey T 13N R 11W _____ C-1 _____
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

VOL. 2 233

Register of Deeds Stamp & File Number

	A	B	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Norman L. Ochs, in a field survey on October 22, 19 98, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Northwest Corner, Section 5, Big Prairie Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. John Hodgson 1837
24" Pine S46°W 17 Links (11.22') #1
24" Pine S74°E 39 Links (25.74') #2

Lyle S. Shepherd R.L.S. #503
Book 95 Page 27 1922
2" Wood Stake
10" Oak N51°30'E 35.2' #3
24" Oak S25°30'W 132.5' #4

Newaygo County Road Commission Sheet
Reinforced Rod
18" Black Oak S42°W 90.2' #5
Power Pole N47°W 48.00' #6
16" White Oak N65°E 51.2' #7

Patrick A. Salisbury R.L.S. #13594
October 16, 1972 Found 1/2" Rod
Southeast Corner, Section 31, T14N R11W East 19.68' #10
Power Pole N50°W 48.39' #6
12" Pine S40°E 42.36' #8
Guy Pole S45°W 56.49' #9

Robert A. Griffin R.L.S. #13584
1977 Found "P.K." spike in pavement
Southeast Corner, Section 31, T14N R11W, (1/2" Pipe) East 19.68' #10

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 1/2" X 18" Rerod next to a 1/2" (on top) X 24" (1" on bottom) Rod that was thru an old steel Axle Mount on line ± with the centerline of the East and West bituminous road and on line ± with the centerline of the gravel road going South. The condition of the recorded witnesses are: #1 thru #4 gone, #5 stump, #6 good condition, #7 and #8 gone, #9 and #10 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed Rerod, Rod and Axle Mount and set a 2 3/4" X 20" Harrison cast iron monument marked "County Survey" in new 8" diameter monument box as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

Power Pole N47°W 48.35' Found spike in Northeasterly side of pole (also Forest Service locator Poster) #6
Guy Pole S46°W 56.51' Found spike in Southeasterly side of pole (also Forest Service locator Poster) #9
Southwest Corner, Section 32, T14N R11W, East 19.68' #10
20" Red Pine S40°E 60.37' Found spike in Northeasterly side of tree.
1/2" Rerod N57°E 62.31'
24" - 26" Twin Black Oak N68°E 106.20' Set spike with tag #22439 in South side of tree.

Signed by Norman L. Ochs Date November 3, 1998

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors No. 22439, 1998

Approved by Peer Review Group on December 8, 1998
Norman L. Ochs, County Representative.



N.L.O.