

MAR 02 1999

1998 Newaygo County Remonumentation Project

LAND CORNER RECORDATION CERTIFICATE '99 FEB 17 PM 3 39 FILING REQUIREMENT of Act 74, Mich. P.A. 1970

SECTION

Linda M. Brown

VOL. 2 234

For corners in Newaygo (County) Located in: Corner Code # 1. Public Land Survey T 13N R 11W D-1 2. Property Controlling in Section S T R 3. Miscellaneous Property in Sec. S T R 4. Lot No. , Recorded Plat 5. Private Claims

Register of Deeds Stamp & File Number

Grid with columns A-M and rows 1-13. Cell (1, D) is shaded.

I, Norman L. Ochs, in a field survey on October 22, 1998, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

North One Quarter Corner, Section 5, Big Prairie Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

- G.L.O. Not Set. Patrick A. Salisbury R.L.S. #13594 1972 Found Reinforced Rod 18" Maple S28°E 34.8' #1 24" White Oak N62°W 63.6' #2 Southeast Corner House N14°E 65.0' #3

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 1/2" X 21" Rerod, 3/4" X 24" Rerod and a 3/4" X 28" Shaft with a 1" hexagon head (all right next to each other and held the 1/2" Rod for position which was above the stone) and a large stone 0.5 feet ± south (10" X 10" X 10"). The centerline of the East and West bituminous road is 1 foot North and the centerline of the two-track going South is 2 feet East. The condition of the recorded witnesses are: #1 thru #3 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed Rerod, Shaft and Stone and set a 2 3/4" X 20" Harrison cast iron monument marked "County Survey" in a new 8" diameter monument box as a substantial marker for the section corner.

- 48" Maple (blazed) S28°E 34.20' Set spike with tag #22439 in West side of tree. #1 26" White Oak N60°W 64.64' Set spike with tag #22439 in South side of tree. #2 Southeast Corner Concrete Foundation House #5993 N15°E 65.04' #3 Power Pole N68°E 70.26' Found spike with tag (illegible) in Northwesterly side of pole. South One Quarter Corner, Section 32, T14N R11W, East 23.17'

Signed by Norman L. Ochs Date November 3, 1998

Surveyor's Michigan License No. 22439 Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Approved by Peer Review Group on November 10, 1998 Norman L. Ochs, County Representative. Revised May 14, 1975 Revised Jan., 1983

