

SURVEY & REMONUMENTATION

MAR 02 1999

1998 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970 '99 FEB 17 PM 3 39

SECTION

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>13N</u> R <u>11W</u>	<u>G-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Linda M. Brown

VOL. 2

237

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Norman L. Ochs, in a field survey on July 15, 1998, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Northeast Corner, Section 4, Big Prairie Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. John Hodgson 1837
10" White Oak S33°E 40 Links (26.40') #1
12" White Oak S85°W 51 Links (33.66') #2
Southeast Corner, Section 33, T14N R11W,
East 46.20' #8

Norman L. Ochs R.L.S. #22439
September 8, 1978 Set 1/2" Rod on line between the South One Quarter Corner and the Southeast Corner of Section 33, T14N R11W, and at G.L.O. distance.
6" White Pine S11°W 50.39' #5
8" Red Oak N58°E 68.27' #6
5" Red Oak N24°E 55.56' #7
Southeast Corner, Section 33, T14N R11W, East 46.20' #8

Newaygo County Road Commission Sheet
18" Pine Northeast 41.2' #3
8" Pine Southeast 22.3' #4

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 1/2" X 13" Rerod and the centerline of the East and West bituminous road is 1 foot South and the fence line going South is 36 feet ± East. The condition of the recorded witnesses are: #1 thru #4 gone, #5 thru #8 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed Rerod and set a 2 3/4" X 20" Harrison cast iron monument marked "County Survey" in new 8" diameter monument box as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

12" White Pine (blazed) S11°W 50.65' Set spike with tag #22439 in West side of tree. #5
12" Red Oak N53°E 68.23' Found spike in Westerly side of tree. #6
12" Red Oak N20°E 55.77' Set spike with tag #22439 in East side of tree. #7
Southeast Corner, Section 33, T14N R11W (2 3/4" X 20" Harrison cast iron monument in monument box) East 46.20' #8

Signed by Norman L. Ochs Date October 20, 1998
Norman L. Ochs

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971
Revised May 14, 1975
Revised Jan., 1983

Approved by Peer Review Group on November 10, 1998
Norman L. Ochs, County Representative.

N.L.O.

