

MAY 28 1997

COMMISSION

1996 Newaygo County Remonumentation Project

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

'97 FEB 12 PM 4 45

Linda M. Brown

For corners in Newaygo (County) Located in: Corner Code #

1. Public Land Survey T 13N R 11W G-3
 T ___ R ___
 T ___ R ___
 T ___ R ___

2. Property Controlling in Section S ___ T ___ R ___
 S ___ T ___ R ___

3. Miscellaneous Property in Sec. S ___ T ___ R ___
 S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

VOL. 1 PAGE 234

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	0		5		4		3		2		1		
3							●						
4	7		0		0		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Norman L. Ochs, in a field survey on October 1, 1996, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Northwest Corner, Section 10, Big Prairie Township, Newaygo County, Michigan

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. James H. Mullett 1839
 8" White Oak N44°W 32 Links (21.12') #1
 10" White Oak S71°E 42 Links (27.72') #2

Ralph A. Smith R.L.S. #3421
 Book 70 Page 136 August 9, 1951
 Set Drive shaft from 1895 old witness
 16" White Oak N17°E 59.4' #3
 20" Pine Stump N54½°W 44.88' #4
 8" White Pine N50°±W 45.3' #5
 8" White Oak N85°±W 40.9' #6

William M. Jacques (County Surveyor)
 Book 14 Page 41 1904
 Stake with an old axe buried at bottom of stake

Newaygo Engineering and Survey Company
 May 2, 1977 Found 5/8" Rod
 16" White Pine S76°E 56.08' #7
 10" White Oak N56°E 48.82' #8
 28" White Oak N67°W 45.46' #9

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 5/8" Rod, Axle Shaft with clay pieces (crocker) and metal hay (2) cutting blades ±1 foot deep and the centerline of the North and South road is 9 feet East and old fence going East is 1.5 feet North and on line with old fence going West and the condition of the recorded witnesses are: #1 thru #6 gone, #7 thru #9 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed Axle Shaft and set a 4" diameter Harrison cast iron monument 20" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

24" White Pine S76°E 56.08' Set spike in North side of tree. #7
 16" White Oak N56°E 48.9' Found spike in Northwest side of tree. #8
 28" White Oak N67°W 45.46' Found spike in Northeast side of tree. #9
 10" White Pine S50°E 48.65' Set spike and tag in Northeast side of tree.

Signed by Norman L. Ochs Date October 17, 1996

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971
 Revised May 14, 1975
 Revised Jan., 1983

Approved by Peer Review Group On October 24, 1996
 Norman L. Ochs, County Representative.

N. L. O.

