

COMMISSION

1996 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

'97 FEB 12 PM 4

Linda M. Brown

Form with fields: For corners in Newaygo (County), Located in: T 13N R 11W, Corner Code # G-5, 1. Public Land Survey, 2. Property Controlling in Section, 3. Miscellaneous Property in Sec., 4. Lot No., 5. Private Claims

VOL. 1 PAGE 236

Register of Deeds Stamp & File Number table with columns A-M and rows 2-13. A black dot is present in the cell for row 5, column F.

I, Norman L. Ochs, in a field survey on October 2, 1996, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Southwest Corner, Section 10, Big Prairie Township, Newaygo County, Michigan

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

- G.L.O. James H. Mullett 1839 10" White Oak N37°E 25 Links (16.5")#1 10" White Oak N55°W 38 Links (25.08")#2 William M. Jacques (County Surveyor) 1904 Book 14 Page 41 Broken Crockery ware around stake Delos G. Anderson (County Surveyor) Book A Page 348 July 18-19, 1902 14" White Oak S17°E 18'4" (18.33")#3 Lyle S. Shepherd R.L.S. #503 July 15, 1926 Book 21 Page 128 Set Tile-replaced old stake, crockery and iron 14" White Pine N54 1/4°E 72 Links (47.52")#4 8" White Oak S70 1/4°E 1.00 1/4 Chains (66.17")#7 Lyle S. Shepherd R.L.S. #503 Consumers Power Company Book 59A Page 3 October 15, 1925 Found Ax Haive and remains of old stake below 12" Yellow Pine N54°45'E 72 Links (47.52")#4 Fence Post N43°15'W 63 1/2 Links (41.91")#5 8" Yellow Pine S76°45'W 226 Links (149.16")#6 NCRC Sheet Concrete Monument 12" Black Oak S04°E 52.7' #8 10" Black Oak S23°W 70.8' #9 10" Pine N32°E 94.8' #10

OVER

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 1/2" Rod and Tile filled with concrete and the centerline of the road going East and West is 3.9 feet North and the centerline of the road going North is 5 feet East and the centerline of two-track going South is 22 feet East and the condition of the recorded witnesses are: #1 and #2 gone, #3 and #4 in cut area, #5 and #6 gone, #7 thru #9 good condition, #10 gone, #11 thru #13 good condition, #14 thru #17 gone, #18 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Replaced 1/2" Rod, and Tile with a 4" diameter Harrison cast iron monument 20" long marked "County Surveyor" in the exact position as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

- 12" White Oak S70 1/4°E 66.17' Set spike and tag in Northeast side of tree. #7 16" Black Oak S04°E 53.36' Found nail in West side of tree. #8 16"-16" Twin Black Oak S23°W 71.07' Found spike in East side of tree. #9 18" Red Oak S02°W 31.95' Set spike and tag in East side of tree. #11 Utility Pole N41°E 53.48' Spike in East side of pole. #12 Telephone Pole N29°W 54.47' Found spike and tag #30389 in Northeast side of pole. #13 Telephone Pole N29°W 53.56' Spike in East side of South pole. Concrete Monument South 33.02' #18 Found Nail N50°E 16.72' North edge of road.

Signed by Norman L. Ochs Date October 17, 1996

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971 Revised May 14, 1975 Revised Jan., 1983

Approved by Peer Review Group On October 24, 1996 Norman L. Ochs, County Representative.

N. L. O.



A. Description (cont.)

Ralph A. Smith R.L.S. #3421
Book 70 Page 143 December 5, 1961 Found Tie
14" White Pine N54 $\frac{3}{4}$ °E 47.5' #4
8" White Oak S70 $\frac{3}{4}$ °E 66.2' #7
12" Red Oak S02°W 31.3' #11

Clinton E. Cole R.L.S. #17615
December 20, 1974 Recorded in Series G Number 9133
Utility Pole N41°E 53.43' #12
Telephone Pole N29°W 53.60' #13
12" Black Oak S04°W 33.03' #11

Patrick A. Salisbury R.L.S. #13594
1974 Found $\frac{1}{2}$ " Rod
12" Black Oak S04°E 53.35' #8
8"-10" Twin Black Oak S23°W 71.20' #9
Power Pole N41°E 53.50' #12
Guy Pole N30°W 53.65' #13

Newaygo Engineering and Survey Company 1983
 $\frac{1}{2}$ " Rod and Cap North 33.00' #14
Clump Ash N01°W 54.0' #15
Power Pole S36°W 85.00' #16

William Fries Jr. R.L.S. #30389
May 22, 1990 LCRC #1019
Found $\frac{1}{2}$ " Iron in occupied centerline of road to North and 4' South of occupied centerline of road to East and West
Power Pole N38°E 53.24' #12
12" Pine N53°E 99.45' #17
Concrete Monument South 33.01' #18
Power Pole N32°W 54.46' #13