

MAR 02 1999

1998 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

SECTION

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

'99 FEB 17 PM 3 39

Linda M. Brown

VOL. 2

238

For corners in Newaygo (County) Located in: Corner Code #

1. Public Land Survey T 13N R 11W H-1
 T ___ R ___
 T ___ R ___
 T ___ R ___

2. Property Controlling in Section S ___ T ___ R ___
 S ___ T ___ R ___

3. Miscellaneous Property in Sec. S ___ T ___ R ___
 S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on July 14, 1998, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

North One Quarter Corner, Section 3, Big Prairie Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Not set. No previous history.

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found no monument at this position. Established corner equal distance between the Northeast Corner and the Northwest Corner, Section 3, T13N R11W and on line with the South One Quarter Corner and the Southwest Corner, Section 34, T14N R11W. The centerline of the East and West bituminous road is 0.5 feet ± North and wood fence posts going South are 14 feet ± West.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Set a 2 3/4" X 20" Harrison cast iron monument marked "County Survey" in a salvaged 8" diameter monument box as a substantial marker for the section corner.

- 22" Red Oak (blazed) N19°E 51.78' Set spike with tag #22439 in West side of tree.
- 20" Red Oak (blazed) N11°W 56.20' Set spike with tag #22439 in West side of tree.
- 10" Red Pine (blazed) S35°E 77.83' Set spike with tag #22439 in East side of tree.
- 6" Red Pine (blazed) S02°W 58.88' Set spike with tag #22439 in Easterly side of tree.
- South One Quarter Corner, Section 34 (2 3/4" X 20" Harrison cast iron monument in salvaged monument box) East 39.53'

Signed by Norman L. Ochs Date October 20, 1998
 Norman L. Ochs
 Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971
 Revised May 14, 1975
 Revised Jan., 1983

Approved by Peer Review Group on November 10, 1998
 Norman L. Ochs, County Representative.

N.L.O.

