

**SURVEY & REMONUMENTATION**

MAR 19 1998

1997 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

SECTION

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

'98 MAR 6 PM 12

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>13N</u> R <u>11W</u>	<u>K-11</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*Linda M. Brown*

VOL. 2 96

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on September 17, 1997, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners; all in the same town and range, may be recorded on this certificate.

Northwest Corner, Section 36, Big Prairie Township, Newaygo County, Michigan.

**A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:**

G.L.O. James H. Mullett 1837 8" Beech N31°E 44 Links (9.24')#1 10" Pine S29°E 39 Links (25.74')#2	Ralph A. Smith R.L.S. #3421 Witness Book Number 2 Page 49 Iron 7" Elm S33°±E 25.74' #3 6" Oak N25°±W 31.35' #4
Newaygo County Road Commission Sheet Axle Shaft 24" Black Oak Northeast 50.5' #5 24" Maple S50°E 84.9' #6 7" Elm S33°E 25.74' #3 6" Oak N25°W 31.35' #4	Newaygo Engineering and Survey Company 1978 Drawing Number 77158B Found 1/2" Rod 24" Black Oak N57°E 49.39' #5 24" Maple S55°E 85.17' #6 Power Pole S85°W 37.65' #7
Newaygo Engineering and Survey Company April 24, 1983 Drawing Number 83060AC Found 5/8" Rod 24" Black Oak N57°E 50.63' #5 24" Maple S55°E 86.58' #6 Power Pole S85°W 37.99' #7	

OVER ↙

**B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:**

Found Axle Shaft (50" long - measured 1/2" at top - measured 5/8" at bottom - measured 1 1/4" at center) and found crockery 20" under road bed. The centerline of gravel road going East is 3 feet South and in the centerline of North and South gravel road. The condition of the recorded witnesses are: #1 thru #4 gone, #5 thru #8 good condition.

**C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:**

Removed Axle Shaft and set a 4" diameter Harrison cast iron monument 20" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

42" Black Oak N53°E 50.71' Found spike in Southeast side of tree. #5  
48" Maple S55°E 86.61' Found spike in Northeast side of tree. #6  
Power Pole S76°W 37.98' Found nail in Southeast side of pole. #7  
Power Pole N33°E 72.95' Found nail in West side of pole. #8

Signed by Norman L. Ochs Date October 10, 1997

Surveyor's Michigan License No. 22439 Form approved by Michigan State Board of Land Surveyors, Jan 28, 1991

Approved by Peer Review Group on October 14, 1997  
Norman L. Ochs, County Representative.

*M. L. O.*



A. Description (cont.)

Newaygo Engineering and Survey Company  
January 19, 1996 Drawing Number 96013B  
Found 5/8" Rod  
Power Pole N30°E 72.93' #8  
24" Black Oak N57°E 50.68' #5  
24" Maple S55°E 86.60' #6  
Power Pole S85°W 38.00' #7

John Kistler and Associates  
William Byl  
Undated field notes Found Axle