

SURVEY & REMONUMENTATION

1997 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS
LINDA M. BROWN

MAR 19 1998

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT of Act 74, Mich. P.A. 1970

'98 MAR 6 PM 12 36

Linda M. Brown

For corners in **SECTION**

<u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>13N</u> R <u>11W</u>	<u>K-12</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

VOL. 2

97

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Norman L. Ochs, in a field survey on September 17, 19 97, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

West One Quarter Corner, Section 36, Big Prairie Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. James H. Mullett 1837
8" Beech S43°E 9 Links (5.94') #1
10" Beech N73°W (19.80') #2

Norman L. Ochs R.L.S. #22439
May 17, 1983 LCRC #583

No corner or witnesses found. Set 1" Pipe half way and on line with Northwest and Southwest Section Corners. Old fence going East. In centerline of gravel road North and South.

4" White Pine N45°W 49.58' #3
10" Maple S73°W 48.96' #4
26" Swamp Oak East 56.79' #5

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 1/2" Rod 18" long on old fence line on ground going East. The centerline of North and South gravel road is 2 feet East. The condition of the recorded witnesses are: #1 and #2 gone, #3 thru #5 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed 1 1/2" Rod and set a 4" diameter Harrison cast iron monument 20" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

14" White Pine N59°W 49.50' Found spike in Southwest side of tree. Set spike and tag above found spike. #3
14" Maple S66°W 48.95' Found spike in South side of tree. #4
38" Swamp Oak S85°E 56.84' Found spike in South side of tree. Set spike and tag above found spike. #5
10" White Pine S20°E 53.23' Set spike and tag in tree.

Signed by Norman L. Ochs
Norman L. Ochs

Date October 10, 1997

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Revised May 14, 1975
Revised Jan., 1983

Approved by Peer Review Group on October 14, 1997
Norman L. Ochs, County Representative.

N.L.O.

