

**SURVEY & REMONUMENTATION**

MAR 19 1998

NEWAYGO COUNTY  
REGISTER OF DEEDS  
LINDA M. BROWN

**1997 Newaygo County Remonumentation Project**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT of Act 74, Mich. P.A. 1970**

'98 MAR 6 PM 12 36

*Linda M. Brown*

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>13N</u> R <u>11W</u>	<u>K-13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

VOL. 2

98

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Norman L. Ochs, in a field survey on September 2, 1997, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Southwest Corner, Section 36, Big Prairie Township, Newaygo County, Michigan.

**A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:**

G.L.O. John Hodgson 1837	Norman L. Ochs R.L.S. #22439
8" Pine N62°E 33 Links (21.78') #1	LCRC #582 May 17, 1983
8" White Oak N46°W 54 Links (35.64') #2	Found ¾" Pipe
Newaygo County Road Commission Sheet	1" Pipe, Northwest Corner, Section 1, T12N R11W,
5" Twin Black Oak N30°W 61.6' #3	West 18.06' #5
4" Twin Black Oak S48°E 63.0' #4	Power Pole N20°E 118.28' #6
	8"-10" Twin Black Oak N30°W 61.73' #3
	14" Black Oak S48°E 62.83' #4

**B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:**

Found ¾" Pipe 45" long with crockery around it and a wood stake. The centerline of the North and South gravel road is 9 feet West and the centerline of gravel road going East is 4 feet North and in the centerline of two-track going West. The condition of the recorded witnesses are: #1 and #2 gone, #3 stump, #4 thru #6 good condition.

**C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:**

Removed ¾" Pipe and wood stake and set a 4" diameter Harrison cast iron monument 20" long, with crockery around it, marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

Black Oak Stump N32°W 61.71' center. #3  
22" Black Oak S42°E 62.8' Found spike in Northeast side of tree. #4  
¾" Pipe West 18.00", Northwest Corner, Section 1, T12N R11W. #5  
Power Pole N24°E 118.22' Found spike in Northwest side of pole. #6  
10" White Pine N20°W 74.56' Set spike and tag in Southwest side of tree.

Signed by Norman L. Ochs Date October 10, 1997

Surveyor's Michigan License No. 22439 Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Approved by Peer Review Group on October 14, 1997

Norman L. Ochs, County Representative.

Revised May 14, 1975  
Revised Jan., 1983

*N. L. O.*

