

**SURVEY &
REMONUMENTATION**

APR 24 1995 1994 NEWAYGO COUNTY REMONUMENTATION PROJECT

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **COMMISSION**
Newaygo
(County)

VOL **001** PAGE **105**

	Located In:	Corner Code #
1. Public Land Survey	T <u>13N</u> R <u>11W</u>	M-2
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

NEWAYGO COUNTY
REGISTER OF DEEDS
MARLENE TOOGOOD

'95 MAR 14 PM 3 55
Register of Deeds Stamp & File Number

Marlene Toogood

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

I, Norman L. Ochs, in a field survey on December 14, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

E. 1/4 Corner, Section 1, Big Prairie Twp., Newaygo Co., MI

A. Description of original monument and accessories and/or subsequent restoration:
G.L.O. John Hodgson 1837
A 12" Hemlock for corner #1

OVER----->

Lyle S. Shepherd R.L.S. #503 1920's Set a 2" Pipe with Consumers Power Co. cap (Standard Marker) 16" Pine Stump N25 1/2°E .59 3/4 ch. (39.44') #2 5" W. Oak S83°W .36 ch. (23.76') #3
Did section break for Consumers Power Co. Drawing No. 164-F-1343-3H14. He prorated the East section line to set the E. 1/4 Cor. Measured 40.45 ch. (2669.70 feet) from the N.E. Cor. to the E. 1/4 Cor. of Sec. 1 and measured 40.28 1/2 ch. (2658.81 feet) from the E. 1/4 Cor. to the S.E. Cor. of Sec. 1.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 2" Pipe with Consumers Power Co. Cap and condition of recorded witnesses are: #1 and #2 Gone, #3 thru #6 Good Condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted 2" Pipe with Consumers Power Co. Cap as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.
12" W. Oak S83°W 23.69' Spike in South side of tree #3
20" B. Oak S27°W 54.10' Spike in S.E. side of tree #4
24" R. Oak N70°W 36.12' Spike in South side of tree #5
8" Twin Maple N32°E 39.60' Spike in N.W. side of tree #6



Signed by Norman L. Ochs Date December 15, 1994
Surveyor's Michigan License No. #22439

Approved by Peer Review Group on December 15, 1994
Norman L. Ochs, County Representative. *N.L.O.*

A. Description.....(Continued)

Newaygo Engineering and Survey Co. October 1993

Found 2" Pipe - Consumers Power Co. Standard Marker

20" B. Oak S27°W 54.10' #4

12" W. Oak S83°W 23.69' #3

24" R. Oak N70°W 36.12' #5

8" Tw. Maple N32°E 39.60' #6

Measured 2661.18 feet from the N.E. Cor. to the E. 1/4 Cor. of Sec. 1 and measured 2658.31 feet from the E. 1/4 Cor. to the S.E. Cor. of Sec. 1.