

LAND CORNER RECORDATION CERTIFICATE 94 JAN 21 PM 3 26
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

NEWAYGO

(County)

Located In:

Corner Code ##

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>13N</u> R <u>12W</u> | <u>A-1</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |

Marlene Toogood

VOL 001 PAGE 21

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on November 1, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

NW Corner, Sec Everett Twp., Newaygo County, MI

A. Description of original monument and accessories and/or subsequent restoration:

- | | | |
|-----------------------------|---------------------------------------|---|
| GLO John Hodgson 1837 | Oct 1958 R A Smith | 1973 R A Griffin LCRC #691 |
| 16" Pine N41°W 16' lks : #1 | 3/4" Pipe | 5" Sq x 36" conc mon C. Cole #17615 |
| 19" Pine S33°E 16' lks : #2 | 18" Pine S80°W 61.8' #6 | 5" W Oak N51°E 89.26' #9 See L. 349 |
| | 17" W Oak N25°E 66.6' #7 | 8" W Oak S27°E 49.50' #10 Also Pg. 2698 |
| 1938 R A Smith | 10" B Oak N45°W 66.1' #8 | 17" R Pine S55°W 61.89' #11 |
| Gas Pipe | Nov 1975 DNR | 4'x7" Post N 33.26' #12 |
| 24" B Oak S+ 32.4' #3 | 5" sq. x 86" conc mon | |
| 15" Pine S55°W 61.7' #4 | Same witnesses as R A Griffin in 1973 | |
| 14" W Oak N25°E 67.2' #5 | | |


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found gas pipe by R. A. Smith
 R. A. Griffin in 1973 set 5" sq. x 36" conc. mon, 3-1/2' North of CL of East and West road.
 Found Griffins conc. mon. in good condition raised with 1/2" rod 6" long.
 Condition of recorded witnesses is: #1 gone, #2 gone, #3 gone, #4 good condition, #5 good condition, #6, gone, #7 good condition, #8 gone, #9 good condition, #10 good condition, #11 good condition, #12 gone.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted R. A. Griffins conc. mon. raised with 1/2" rod 6" long as a substantial marker for the Section corner, and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 20' W. Oak N25°E 67.47' Spk. #5, #7
- 6" W. Oak N51°E 89.26' Spk. #9
- 12" W. Oak S27°E 49.50' Spk. #10
- 20' W. Pine S55°W 61.80' 1/4" iron in tree #6, #11



Signed by Norman L. Ochs
 Norman L. Ochs
 Surveyor's Michigan License No. 22439

Date November 8, 1993

Approved by Peer Review Group Nov. 9, 1993
 Norman L. Ochs, County Representative

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN. 1983

SURVEY &
 REMONUMENTATION

DEC 07 2000

SECTION