

**SURVEY & REMONUMENT**

MAY 28 1997

COMMISSION

1996 Newaygo County Remonumentation Project

LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT of Act 74, Mich. P.A. 1970

NEWAYGO COUNTY  
REGISTER OF DEEDS  
LINDA M. BROWN

'97 FEB 12 PM 4 45

*Linda M. Brown*

For corners in  
Newaygo  
(County)

Located in: \_\_\_\_\_ Corner Code # \_\_\_\_\_


1. Public Land Survey T 13N R 12W  
T 13N R 13W  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_



VOL. 1 PAGE 242

**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		6		5		4		3		2		1
5													
6	8		7		6		5		4		3		2
7													
8	9		8		7		6		5		4		3
9													
10	10		9		8		7		6		5		4
11													
12	11		10		9		8		7		6		5
13													

I, Norman L. Ochs, in a field survey on December 17, 1996, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

West One Quarter Corner, Section 18, Everett Township, Newaygo County, Michigan  
East One Quarter Corner, Section 13, Sherman Township, Newaygo County, Michigan

**A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:**

G.L.O. John H. Mullett 1837	NCRC Sheet
8" Hemlock S75°W 22 Links (14.52') #1	1 1/2" Pipe
16" Black Ash N29°W 28 Links (18.48') #2	16" Jack Pine S20°E 71.0' #3
Patrick A. Salisbury R.L.S. #13594	10" White Cherry N33°E 40.2' #4
1973 Found 1 1/2" Pipe raised with 1/2" Rod	6" White Cherry N32°W 27.7' #5
10" Cherry N35°E 40.40' #4	
6" Cherry N32°W 27.82' #5	
6" Cherry S89°W 17.76' #6	

**B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:**

Found 1/2" rerod inside of 1 1/4" X 10" Iron Pipe in the centerline of the North and South dirt road and the centerline of culvert is 20.5 feet North and the condition of the recorded witnesses are: #1 thru #3 gone, #4 good condition, #5 and #6 gone.

**C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:**

Removed 1/2" rerod and 1 1/4" X 10" Iron Pipe and set a 4" diameter Harrison cast iron monument 36" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

16" Cherry N37°E 40.44' Found spike in Southeast side of tree. #4  
8" Cherry S82°E 22.54' Set spike and tag in South side of tree.  
12" Elm S32°W 33.36' Set spike and tag in Southeast side of tree.  
8" Red Oak N07°W 75.13' Set spike and tag in East side of tree.

Signed by Norman L. Ochs Date December 20, 1996

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971  
Revised May 14, 1975  
Revised Jan., 1983

Approved by Peer Review Group On December 23, 1996  
Norman L. Ochs, County Representative.

*N. L. O.*

