

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

94 JAN 21 PM 3 26

For corners in
 NEWAYGO

(County)

Located In:

Corner Code #

1. Public Land Survey	T	13N	R	12W	F-1
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Marlene Toogood
 VOL 001 PAGE 30

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	8	7	6	5	4	3	2	1					
7													
8	9	8	7	6	5	4	3	2	1				
9													
10	10	9	8	7	6	5	4	3	2	1			
11													
12	11	10	9	8	7	6	5	4	3	2	1		
13													

I, Norman L. Ochs, in a field survey on December 16, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

N-1/4 Corner, Sec. 4, Everett Twp.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 03-06-93 Norman L. Ochs
 None Fnd. King Bolt #22439
 Wm. M. Jacques 7" W. Pine N23°E 103.22' #1
 Nov. 4, 1904 9" W. Pine S49°E 127.74' #2
 Book B Pg 10 Cor. Fe Post S39°W 67.00' #3
 Set Iron Stake Tel. Riser N33°W 66.28' #4
 NCRC Sheet 5/8" Iron Rod East 9.48' #5
 Monument Box


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In 1896 Delos G. Anderson measures 77.75 Ch (5131.50 ft) from the N-1/4 Cor to the S-1/4 Cor. There are no recorded witnesses. Information was found in book A Pg. 196 at the County Surveyors Office. In 1904 Wm. Jacques broke Sec. 4. He measured S89°39'W, 40.01 Ch (2640.66 ft.) from the N 1/4 Cor. to the NW cor. In 1956 C.F. Zimmerman measured S89°53'W 2639.00' from the N-1/4 cor. to the NW cor. and measured N89°47'E 2644.20' from the N-1/4 cor. to the N.E. cor. and measured S00° 21.9' W 5137.61 ft. from the N-1/4 cor. to the S-1/4 cor. In 1993 Norman L. Ochs measured N89° 21' 28" E 2646.73 ft. from the N-1/4 Cor. to the NE cor. Fnd. King bolt in mon. box replaced with 4" Harrison cast iron mon. Condition of recorded witnesses is: #1 and #2 good condition, #3 and #4 gone, #5 good condition. In 1958 R.A. Smith RLS #3421 measured 2639.86 feet from the N. 1/4 Corner and 2644.20 feet from the N. 1/4 Corner to the NE. Corner.

William Jaques measured N89°39'E 39.97 chains (2638.02 feet) from the N. 1/4 Corner to the NE. Corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted 4" Harrison cast iron monument as a substantial marker for the 1/4 corner and is accepted as a careful and faithful reestablishment of the corner.
 4" Harrison cast iron mon. East 9.48" (S-1/4 cor., Sec. 33, Wilcox Twp.) #5
 8" W. Pine N29°E 103.22' Spike in West side of the tree #1
 12" W. Pine S50°E 128.48' Spike in NE side of the tree #2
 P.Pole S35°W 52.79' Spike in the Westerly side of the pole.
 Guy Pole S25°E 50.57' Spike in West side of the pole.



Signed by Norman L. Ochs
 Norman L. Ochs
 Surveyor's Michigan License No. 22439

Date December 20, 1993

Approved by Peer Group December 21, 1993
 Norman L. Ochs, County Representative

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

SURVEY & REMONUMENTATION

DEC 07 2000

SECTION