

MAR 1 3 2000

1999 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

SECTION

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

FEB 28 PM 1 11

For corners in
Newaygo
 (County)

Located in: Corner Code #

1. Public Land Survey T 13N R 12W G-3
 T ___ R ___
 T ___ R ___
 T ___ R ___

2. Property Controlling S ___ T ___ R ___
 in Section S ___ T ___ R ___

3. Miscellaneous S ___ T ___ R ___
 Property in Sec. S ___ T ___ R ___

Linda M. Brown

VOL. 2

325

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Norman L. Ochs, in a field survey on October 5, 1999, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Southeast Corner, Section 4, Everett Township Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. J.H. Mullett 1837
 12" Cedar S07°W 17 Links (11.22')#1
 12" Ash N60°W 32 Links (21.12')#2

William M. Jacques (County Surveyor)
 September 10, 1906 Book 21 Pages 108-111
 Book B Pages 22 and 25
 Stone Corner

William M. Jacques (County Surveyor)
 November 4, 1904 Book B Pages 10 and 11
 Bearing trees still standing. Set new Post with broken glass and dishes around post.

Newaygo County Road Commission Sheet
 18" Elm S68°W 54.5' #3
 Telephone Pole S38°E 28.1' #4

OVER ↙

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 4" diameter Harrison cast iron monument marked "County Surveyor", 1/2" below bituminous, on line ± with the centerline of the East and West bituminous road. The centerline of the gravel road going North is 4 feet East. There is no apparent occupation going South. The condition of the recorded witnesses are: #1 thru #4 gone, #5 thru #8 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Accepted 4" diameter Harrison cast iron monument 36" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

- 10" Cedar (blazed) S08°W 27.88' Found spike in East side of tree. #5
- 6" - 12" Twin Cedar (blazed) S49°E 44.77' Found spike in Easterly side of tree. #6
- 5 trunks - 6" - 14" Clump Basswood (blazed) N37°E 41.06' Set spike with tag #22439 in Southeast side of tree. #7
- Telephone Riser N37°W 33.48' To center. #8
- 8" Ash (blazed) N28°W 47.25' Set spike with tag #22439 in Southwesterly side of tree.

Signed by Norman L. Ochs Date October 22, 1999

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971
 Revised May 14, 1975
 Revised Jan., 1983

Approved by Peer Review Group On October 28, 1999
 Norman L. Ochs, County Representative.

N. L. Ochs



A. Description (cont.)

Patrick A. Salisbury R.L.S. #13594
May 20, 1974 Found 3/8" Rod raised with 1/2" Pipe
20" Elm Stump S70°W 54.5' #3
6" Cedar S20°W 27.76' #5
Twin Cedar S46°E 44.95' #6
(3) 8" and (2) 3" Clump Basswood N41°E 41.24' #7
Telephone Riser N45°W 33.68' #8

SURVEY &
REMONUMENTATION

MAR 13 2000

SECTION

Norman L. Ochs R.L.S. #22439
Drawing Number 77137AC August 10, 1977
Found 3/8" Rod
6" Cedar S20°W 27.76' #5
Twin Cedar S46°E 44.95' #6
(3) 8" - (2) 3" Clump Basswood N41°E 41.24' #7

Norman L. Ochs R.L.S. #22439
October 18, 1990 LCRC #1054
Found 3/8" rod in 1/2" Pipe - Removed and set a 4" diameter Harrison cast iron monument 36 " long marked "County Surveyor"
Telephone Riser N45°W 33.68' #8
(3) 8" - (2) 3" Clump Basswood N41°E 41.13' #7
6" - 12" Twin Cedar S46°E 44.80' #6
6" Cedar S20°W 27.89' #5