

**SURVEY & REMONUMENTATION**

MAR 19 1998

SECTION

1997 Newaygo County Remonumentation Project

LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT of Act 74, Mich. P.A. 1970

NEWAYGO COUNTY  
REGISTER OF DEEDS  
LINDA H. BROWN

'98 MAR 6 PM 12 36

*Linda M. Brown*

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>13N</u> R <u>12W</u>	<u>H-13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

VOL. 2

95

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Norman L. Ochs, in a field survey on September 11, 19 97, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

South One Quarter Corner, Section 34, Everett Township, Newaygo County, Michigan.

**A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:**

G.L.O. John Hodgson 1837  
8" Black Oak N25½°E 203 Links (133.98')#1  
14" White Oak N48¾°W 233 Links (153.78')#2

Patrick A. Salisbury R.L.S. #13594  
October 24, 1974 Set concrete monument half way on line between the Southwest Corner and the Southeast Corner.

7" White Pine N55°E 52.35' #3  
10" Black Oak S47°E 56.65' #4  
16" Oak N73°W 119.25' #5

Measured 2655.40 feet from the South One Quarter Corner to the Southwest Corner of Section 34 and measured 2697.28 feet from the South One Quarter Corner to the Center One Quarter Corner of Section 34. Measured 2655.40 feet from the South One Quarter Corner to the Southeast Corner of Section 34.

**B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:**

Found 1¼" Pipe 6 feet long. Fence going North and South is 7 feet West and fence going East is 50 feet North and centerline of trail road going Northeasterly and Southwesterly is N73°W 78 feet. The condition of the recorded witnesses are: #1 and #2 gone, #3 and #4 good condition, #5 stump.

**C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:**

Removed 1¼" Pipe and set a 4" diameter Harrison cast iron monument 20" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

16" White Pine N60°E 52.35' Set spike and tag in centerline of tree. #3  
18" Black Oak S47°E 56.65' Set spike and tag in South side of tree. #4  
16" Black Oak Stump N73°W 119.25' to center of stump. #5  
16" White Pine N02°E 35.98' Set spike and tag in West side of tree.  
12" White Pine S43°W 54.48' Set spike and tag in Northwest side of tree.

Signed by Norman L. Ochs Date October 7, 1997  
Norman L. Ochs

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971  
Revised May 14, 1975  
Revised Jan., 1983

Approved by Peer Review Group on October 14, 1997  
Norman L. Ochs, County Representative.

*M. L. O.*

