

MAR 13 2000

1999 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS
LINDA M. BROWN

SECTION

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT of Act 74, Mich. P.A. 1970

00 FEB 28 PM 1 11

Linda M. Brown

VOL. 2

329

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>13N</u> R <u>12W</u>	<u>I-11</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on November 24, 1999, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Northeast Corner, Section 34, Everett Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. J.H. Mullett 1837
18" Pine S45°W 50 Links (33') #1
12" White Oak N64°W 95 Links (62.7') #2

Norman L. Ochs R.L.S. #22439
April 24, 1979 Drawing Number 79044B
Found 5/8" Rod in monument box in centerline of road going South and in centerline of trail going North. The centerline of the East and West blacktop road is 1.40' North.
22" Black Oak S44°W 57.38' #3
18" - 18" Twin Black Oak N21°E 51.24' #4
10" White Oak S44°E 82.03' #5

Newaygo County Road Commission Sheet
Iron
18" Black Oak S44°W 56.75' #3
14" Twin Black Oak N21°E 50.5' #4
10" White Oak S44°E 81.9' #5

Norman L. Ochs R.L.S. #22439
December 5, 1990 LCRC #1073
Found 5/8" Rod in 1" Pipe in monument box. Removed and set a 4" diameter Harrison cast iron monument marked "County Surveyor" in monument box.
22" Black Oak S44°W 57.32' #3
18" - 18" Twin Black Oak N21°E 51.30' #4
10" White Oak S44°E 82.04' #5
10" Black Oak N45°W 43.38' #6

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 4" diameter Harrison cast iron monument 16" long marked "County Surveyor" in monument box. On line ± with the centerline of gravel road going South and on line ± with the centerline of two track going North and the centerline of the East and West bituminous road is 1 foot ± North. The condition of the recorded witnesses are: #1 and #2 gone, #3 thru #6 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Accepted 4" diameter Harrison cast iron monument 16" long marked "County Surveyor" in 8" diameter monument box as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

34" Black Oak (blazed) S42°W 57.20' Found spike in East side of tree. #3
24" - 28" Twin Black Oak (blazed) N20°E 51.34' Found spike in West side of tree. #4
14" White Oak (blazed) S44°E 82.02' Found spike in North side of tree. #5
14" Black Oak (blazed) N23°W 43.41' Found spike in West side of tree. #6

Signed by Norman L. Ochs Date November 30, 1999

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors

Approved by Peer Review Group on November 30, 1999
Norman L. Ochs, County Representative.



Norman L. Ochs