

# SURVEY & REMONUMENTATION

APR 24 1995 1994 NEWAYGO COUNTY REMONUMENTATION PROJECT

## LAND CORNER RECORDATION CERTIFICATE

**COMMISSION**

Filing Requirement of Act 74, Mich. P.A. 1970

VOL **001** PAGE **110**

For corners in

<u>Newaygo</u> <small>(County)</small>	Located in:	Corner Code #	
1. Public Land Survey	T <u>13N</u> R <u>12W</u>	<u>K-13</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

NEWAYGO COUNTY  
REGISTER OF DEEDS  
MARLENE T-00600D

'95 MAR 14 PM 3 56

Register of Deeds Stamp *Original*

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Norman L. Ochs in a field survey on October 29, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

SW. Corner, Section 36, Everett Twp., Newaygo Co., Mich.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. John Hodgson 1837  
10" B. Oak N88°E 12.87 lks. (8.49') #1  
8" Cherry N80 1/4°W 6.72 lks. (4.44') #2

W.S. Merrill (Co. Surveyor)  
Book A Page 62 March 10, 1882  
Measured 40.23 Chains (2655.18 feet) from the  
SE. Cor. to the S. 1/4 Cor. of Sec. 35. Measured 39.89 Chains 2632.74  
feet) from the S.E. Cor. to S.E. Cor. to the E. 1/4 Cor. of Sec. 35.

W.S. Merrill (Co. Surveyor)  
Book A. Page 55 and 56  
February 17, 1882  
Measured 39.95 Chains (2636.70 feet) from  
the SW. Cor. to the S. 1/4 Cor. of Sec. 36.

M.C.R.C. 1/2" Iron  
18" W. Pine N57°W 58.8' #3  
16" Cherry N18°E 93.8' #4  
6" Cherry S45°E 65.95' #5

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In October 1994, I, Norman L. Ochs, found Robert A. Griffin's 5" Sq. Reinforced Conc. Post w/brass disk. I measured 2653.59 feet from the SE. Corner to the S. 1/4 Corner of Sec. 35 and Condition of recorded witnesses are: #1 and #2 Gone, #3 Good Condition, #4 Stump, #5 Gone, #6 Good Condition, #7 Gone.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted Robert A. Griffin's 5" Sq. Reinforced Conc. Post w/brass disk as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

- Utility Pole N69°E 112.55' Spike in the NW. side of pole
- 30" W. Pine N57°W 59.55' Spike in SW. side of tree #3
- Cedar Post N45°E 46.7' (Face) #6
- 5" Sq. Reinforced Conc. Post w/brass disk West 3.42' (NE. Cor. of Sec. 2, T12N R12W)
- P. Pole S85°W 136.35' Spike on North side of pole
- 6" W. Pine S50°E 58.76' Spike on S.W. side of tree



Signed by Norman L. Ochs Date November 2, 1994  
Surveyor's Michigan License No. #22439

Approved by Peer Review Group on November 3, 1994  
Norman L. Ochs, County Representative.

A. Description.....(Continued)

Robert A. Griffin R.L.S. #13584 L.C.R.C. #97

Found 1 1/4" by 22" Iron bolt raised w/ 1/2" by 19" Iron Rod. Replaced with a 5" Sq. Reinforced Conc. Post w/brass disk.

16" Cherry N18°E 94.75' #4

5"x7' Cedar Post N45°E 46.7' #6

P. Pole N69°E 111.50' #7

6" Cherry S45°E 66.35' #5

25" W. Pine N57°W 59.55' #3

Center of brass tablet in the Mon. marking the section corner to Sec.'s 1 and 2 on the North line of T12N R12W West 3.96' #8

Newaygo Engineering and Survey Co.

Book 70A Page 60 December 10, 1964

24" Pine N57°W 59.55' #3

Post N45°E 49.6' #6

Newaygo Engineering and Survey Co.

October 4, 1979 Found Conc. Mon.

16" Cherry N18°E 94.75' #4

5" Cedar Post N45°E 46.7' #6

6" Cherry S45°E 66.35' #5

Measured 2636.41 feet from the SE. Cor. to the E. 1/4 Cor. of Sec. 35. Measured 2642.52 feet from the SW. Cor. to the S. 1/4 Cor. of Sec. 36. Measured 5285.05 feet from the SW. Cor. to the SE. Cor. of Sec. 36. Measured 3.42 feet from the SE. Cor. of Sec. 35 West to the NE. Cor. of Sec. 2, T12N R12W.