

1993 NEWAYGO COUNTY REMONUMENTATION PROJECT  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

*Marlene Toogood*  
VOL 001 PAGE 28

For corners in  
Newaygo  
(County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>13N</u> R <u>12W</u>	<u>L-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on December 16, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

N. 1/4 Corner, Section 1, Everett Twp., Newaygo County, Michigan'

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. NONE

N.C.R.C. Sheet

Iron

Ralph A. Smith R.L.S. #3421 8 Elm S01°W 45.0' #1

Field Book 81B Page 41 and 42' 14" Elm S50°W 57.5' #2

Iron July 7, 1958

8" Elm S01°W 45.0' #1

14" Elm S50°W 57.5' #2

8" Maple S66°E 75.9' #3

Newaygo Engineering & Survey Co.

May 21, 1974 1/2" Rod

10"-6" Tw. Maple N27°E 81.61' #4

10"-5" Tw. Maple S02°W 57.63' #5

Newaygo Engineering & Survey Co.

July 31, 1980 Found 1/2" Pipe

and Cap

8"-12" Tw. Maple S10°W 57.89' #5

8-6" Tw. Maple AZ 120°69.65' #6

12"-6" Tw. Maple N21°E 79.21' #4

12" -6" Tw. Maple S63°E 76.10' #3

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In 1958 Ralph A. Smith broke Sec. 1, Everett Twp. He measured S88°12'30"W 2649.53 feet from the N. 1/4 Corner to the NW. Corner and measured N88°17'20"E 2650.72 feet from the N. 1/4 Corner to the NE. Corner. Smith measured S00°04'32"W 5203.18 feet from the N. 1/4 Corner to the S. 1/4 Corner. In 1974 Newaygo Eng. and Survey Co. found old 1/2" rod, which was located 0.50 feet South of the centerline of the East and West Blacktop Road. They rebroke the section. They measured S89°10'41"W 2651.58 feet from the N. 1/4 Corner to the NE. Corner and measured S01°02'41"W 5203.73 feet from the N. 1/4 Corner to the S. 1/4 Corner. In 1980 Newaygo Eng. and Survey Co. found the S. 1/4 Corner of Section 36, Wilcox Twp. to be East 6.60 feet.

Found 1/2" Pipe. Replaced with 4" Harrison Cast Iron Monument

Condition of recorded witnesses is; #1 and #2 Gone #3 thru #5 Good Condition #6 Gone

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted 4" Harrison Cast Iron Monument as a substantial marker for the 1/4 Corner and is accepted as a careful and faithful reestablishment of the original corner.

S. 1/4 Corner. Sec. 36, Wilcox Twp. East 6.60'

8"-10" Tw. Maple N28°E 81.57' Spike in West side of tree #4

12"-10" Maple S62°E 75.97' Spike in SW. side of tree #3

10"-6" Maple S03°W 57.63' Spike in East side of tree #5



Signed by Norman L. Ochs  
Norman L. Ochs

Date December 16, 1993

Surveyor's Michigan License No. #22439

Approved by Peer Group December 29, 1993

Norman L. Ochs, County Representative

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN. 1983

SURVEY &  
REMONUMENTATION

DEC 17 2000

SECTION