

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

'94 JAN 21 PM 3 26

Marlene Toogood

For corners in

NEWAYGO (County) Located In: Corner Code=# 1. Public Land Survey T 13N R 12W M-9 2. Property Controlling in Section S T R 3. Miscellaneous Property In Sec. S T R 4. Lot No. Recorded Plat 5. Private Claims

VOL 001 PAGE 25

Register of Deeds Stamp & File Number

I, Norman L. Ochs, in a field survey on November 5, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. Contains numbers 6-36.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

SE Corner, Section 24, Everett Twp., Newaygo County, MI A. Description of original monument and accessories and/or subsequent restoration: G.L.O. J. Hodgson 1837 3-28-67 Salisbury & Sanders 28" W. Oak S79°W 95 lks #1 3/4" Pipe 12" W. Oak N73°W 60 lks #2 20" Tw. Oak N87°W 55.25' #5 B.36, Pg. 88 16" B. Oak S54°W 62.70' #6 Lyle Shepherd's Book 1916 SW Cor. Tower N26°E 92.30' #7 14" B. Oak N32-1/2°E 52.5' #3 6-13-77 R.A. Griffin Set Monument 8" B. Oak N16-1/4°E 122' #4 16" B. Oak S54°W 63.09' #8 Found old stone. 7" R. Pine S70°W 109.35' #9 P. Pole N19°W 105.11' #10

9-16-85 New. Eng. & Sur. Co. R.A.G. Monument 4" x 4" Post West 33.05' #12 30' x 12" Tw. B. Oak West 56.44' #13 10" R. Pine S70°W 109.31' #14 14" B. Oak S54°W 63.07' #15

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: 1990 A. L. Meyer RLS #15488 Monument L.C.R.C. #1006 16" B. Oak S54°W 63.09' #16 N.C.R.C. Sheet Stone & Old Stake S.W. Leg. Tower N28°E 92.0' 7" R. Pine S70°W 109.35' #17 10" B. Oak West 56.2' P.Pole N19°W 105.35' #18 NW Cor. Old Fnd. Wall S.E. 114.0' 4" x 7' Post West 33.07' #19 30" B. Oak S80°E 78.8' R. A. Griffin found 3/4" pipe directly over an old, rusted 1/4 x 1 x 12" rusted iron. RLS #13589 Replaced with 5" x 36" conc. monument. LCRC #407 Found conc. monument in good condition.

Condition of recorded witnesses is: #1 gone, #2 gone, #3 gone, #4 gone, #5 good condition, #6 good condition, #7 gone, #8 good condition, #9 good condition, #10 good condition, #11 good condition, #12 good condition, #13 good condition, #14 good condition, #15 good condition, #16 good condition, #17 good condition, #18 good condition, #19 good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: Accepted R. A. Griffin's 5" x 36" conc. monument as a substantial marker for the section corner, and is accepted as a careful and faithful reestablishment of the position of the original corner.

16" B. Oak S54°W 63.09' (Spike in North side of tree) #6, #8, #15, #16, #20 4" x 4" Wood Post West 32.91' (Face) #11, #12, #19, #21 10" R. Pine S70°W 109.35' (Spike in North side of tree) #9, #14, #17, #22. P.Pole N19°W 105.12' (Spike in SW side of pole) #10, #18, #23. 15" B. Oak N87°W 56.45' (Spike in South side of Tree) #5.



Signed by Norman L. Ochs Date November 8, 1993 Surveyor's Michigan License No. 22439

Approved by Peer Review Group Nov. 9, 1993 Norman L. Ochs, County Representative

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971 REVISED MAY 14, 1975 REVISED JAN. 1983

SURVEY & REMONUMENTATION

DEC 07 2000

SECTION