

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

'94 JAN 21 PM 3 26

For corners in

NEWAYGO (County)	Located In:	Corner Code--//
1. Public Land Survey	T 13N R 12W	M-10
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Marlene Toogood
 VOL 001 PAGE 26

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	18	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on November 6, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

E-1/4 Corner, Section 25, Everett Twp, Newaygo County

- A. Description of original monument and accessories and/or subsequent restoration: MI
 1837 G.L.O. John Hodgson NCRS Sheet 6-13-77 R A Griffin
 11" W. Oak S65°W 87 lks. #1 Iron (Plow Point) RLS#13584
 12" W. Oak N73°W 160 lks. #2 SW Cor Tower N20°E 122.9' #5 Set Monument, removed
 Lyle S. Shepherd's Book 1916 Iron N89°W 33.0' #7 1/2" rod
 30" B. Oak S18-1/2°W 109.5' #3 3-28-67 Salisbury & Sanders SW Cor Tower N20°E
 22" B. Oak S70°E 69' #4 Set 1/2" Rod 122.60' #11
 P. Pole N47°E 95.83' #12
 24" B. Oak S78°E 125.65' #9 4" B Oak S57°E 122.33#13
 NE Cor. Bldg. S20°W 88.55 #10 4"x7" Post S45°E 46.59' #14

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 9-16-85 N.E. & S. Co. 1990 A.L. Meyer RLS 15488
 Fnd. R.A.G. Monument Monument LCRC #1006
 30" B. Oak S75°E 126.42' #15 U.S. Wit Post S45°E 46.59' #18
 4"x4" Post S45°E 46.59' #16 6" Oak S30°W 56.89' #19
 P.Pole N47°E 95.83' #17 12" Oak N35°W 73.40' #20
 P.Pole N47°E 95.82' #21


R. A. Griffin on 6-13-77 Found 1-1/2" x 24" rerod directly over an old plow point. Replaced with 5"x36" conc. monument LCRC #407.

Found conc. monument in good condition and accepted for corner as found.

Condition of recorded witnesses is: #1 gone, #2 gone, #3 good condition, #4 gone, #5 good condition, #6 good condition, #7 gone, #8 good condition, #9 good condition, #10 gone, #11 good condition, #12 good condition, #13 gone, #14 good condition, #15 good condition, #16 good condition, #17 good condition, #18 good condition, #19 gone, #20 gone, #21 good condition, #22 good condition, #23 good condition, #24 gone, #25 good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Accepted R. A. Griffins 5" x 36" conc. monument and is a substantial marker for the 1/4 corner, and is accepted as a careful and faithful reestablishment of the position of the original corner.

- S.W. Corner of Tower N25°E 122.56' #5, #8, #11, #22
 P.Pole N49°E 95.89' (Spike in East side of pole) #12, #17, #21, #23.
 31" B. Oak S82°E 126.45' (Nail in SW side of Tree) #6, #9, #15.
 4x4" Fe Post S46°E 46.57' (Spike in East side of Post) #14, #16, #18, #25



Signed by Norman L. Ochs Date November 8, 1993
 Surveyor's Michigan License No. 22439

Approved by Peer Review Group Nov. 9, 1993
 Norman L. Ochs, County Representative

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN. 1983

SURVEY &
 REMONUMENTATION

JEG 07 2000

SECTION