

1983

94 JAN 21 PM 3 25

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

*Marlene Toogood*

For corners in  
NEWAYGO

| (County)                              | Located In:               | Corner Code # |
|---------------------------------------|---------------------------|---------------|
| 1. Public Land Survey                 | T <u>13N</u> R <u>13W</u> | <u>A-1</u>    |
|                                       | T _____ R _____           | _____         |
|                                       | T _____ R _____           | _____         |
|                                       | T _____ R _____           | _____         |
| 2. Property Controlling in Section    | S _____ T _____ R _____   | _____         |
|                                       | S _____ T _____ R _____   | _____         |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____   | _____         |
|                                       | S _____ T _____ R _____   | _____         |
| 4. Lot No. _____, Recorded Plat _____ |                           |               |
| 5. Private Claims _____               |                           |               |

VOL 001 PAGE 19

Register of Deeds Stamp & File Number

I, Norman L. Ochs, in a field survey on December 4, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**  
N.W. Corner, Section 6, Sherman Twp.

A. Description of original monument and accessories and/or subsequent restoration:  
 G.L.O. Mullet Brookfield 1837 Lyle Shepherd's Wit. Book  
 9" Hemlock S29°E 16 lks (10.56') #1 Culv. Post S45°E 33.7'+ #4  
 14" Hemlock N21°W 14 lks (9.24') #2 Cor. Fe Post S43°W 47.3'+ #5  
 Hickory N37-1/2°W 47.3'+ #6  
 Lyle S. Shepherd 6-12-1914  
 Book B, Pg's 58 & 59 NCRC Sheet 2" Pipe  
 Iron Pump & Wood Stake 12" Elm S65°E 79.0' #7  
 10" Water Elm S88-3/4°E 65' #3 10" Elm S65°W 73.9' #8  
 1968 George Blass #5489 Fnd. Spk set 6" Elm N40°W 79.8' #9  
 & used by Salisbury & Sanders

| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 10 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

Salisbury & Sanders 1968  
 Set 1/2" Pipe  
 3/4" Pipe S45°W 48.05' #10  
 P.Pole N40°E 93.60' #11  
 3/4" Pipe S45°E 46.50' #12  
 Sammy S. Barnett 1973  
 Fd 1/2" Pipe R.L.S. #16923  
 P.Pole N45°E 93.92' #11  
 30" Elm Stp. S59°W 61.47' #13  
 St. Sign S38°E 43.6' #14  
 L.C.R.C. #300

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 In 1914 Lyle S. Shepherd found iron pump & wood stake.  
 In 1968 Salisbury & Sanders set 1/2" pipe using the evidence on ground. They did a complete section break of Section 1 of Dayton Twp.  
 Fnd. 1/2" rod & cap and 3/4" pipe. Set 4" Harrison cast iron monument.  
 Condition of recorded witnesses is: #1 thru #10 gone, #11 good cond. #12 thru #14 gone.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Accepted 4" Harrison cast iron monument as a substantial marker for the section corner, and accepted as a careful and faithful reestablishment of the original corner.  
 P.Pole N47°E 94.00' Spike in West side of Pole #11.  
 Tel. Riser S35°E 49.27' Top centerline  
 8" Elm N25°E 113.37' Spike in West side of tree.  
 5" Poplar N30°W 64.54' Spike in NE side of tree.



Signed by *Norman L. Ochs*  
 Norman L. Ochs  
 Surveyor's Michigan License No. 22439

Date December 20, 1993

Approved by Peer Review Group December 27, 1993  
 Norman L. Ochs, County Representative